

02-8708-02-SR

REV. NO. 0

**FINAL DRAFT
SITE INSPECTION REPORT
AUTOTRONIC PRODUCTS
OCEANSIDE, NEW YORK**

PREPARED UNDER

**TECHNICAL DIRECTIVE DOCUMENT NO. 02-8708-02
CONTRACT NO. 68-01-7346**


FOR THE

**ENVIRONMENTAL SERVICES DIVISION
U.S. ENVIRONMENTAL PROTECTION AGENCY**


OCTOBER 15, 1990

**NUS CORPORATION
SUPERFUND DIVISION**

SUBMITTED BY:



**ANTHONY F. CULMONE, JR.
PROJECT MANAGER**



**JENNIFER LEAHY
SITE MANAGER**

REVIEWED/APPROVED BY:



**RONALD M. NAMAN
FACILITY MANAGER**

295655



CONTENTS

Section

- 1 Site Inspection Report Executive Summary
- 2 Environmental Protection Agency Form 2070-13
- 3 Maps
- 4 Conclusions and Recommendations
- 5 Bibliography of Information Sources
- 6 Background Information

SECTION 1

SITE INSPECTION REPORT EXECUTIVE SUMMARY

SITE SUMMARY

Autotronic Products is an active facility located in an industrial/residential area in Oceanside, Nassau County, New York. According to the current owner and operator, Mr. Joseph Spadafina, the facility was constructed in 1951. In 1965, the building was purchased by Union Corporation and in 1982, Mr. Spadafina purchased the facility from Union Corporation. Electronic equipment is designed and manufactured at this facility. The back of the facility is entirely fenced, and access is limited to employees and official visitors. However, other parts of the building have been rented out to various tenants, all of whom have access to common areas including the fenced area.

Between 1981 and 1982, approximately 50 gallons of 1,1,1-trichloroethane (TCA) was illegally dumped on the paved section in the back of the building. The 1,1,1-trichloroethane, which was from a spent cleaning bath, was discarded in 1-quart batches. Once dumped, the waste may have evaporated or run off the pavement. The paved area slopes slightly to the west in the direction of unpaved property owned by the Long Island Railroad.

The illegal dumping ceased in 1982. Autotronic Products was fined \$1,000 by the New York State Department of Environmental Conservation (NYSDEC) and is currently regulated by the Nassau County Health Department (NCHD). The facility produces less than one 55-gallon drum of hazardous waste a year due to slowdown and changes in production processes. Autotronic Products stores its hazardous waste on site. The spent 1,1,1-trichloroethane is collected in drums and stored on pallets in the back of the warehouse. The storage area has been approved by the NCHD. The 1,1,1-trichloroethane, acetone, and paint thinners are hauled away on an as-needed basis by NYSDEC and NCHD-approved waste haulers.

The only other waste management deficiencies or violations noted by the NCHD involved improper temporary waste storage and paperwork deadlines. These violations were corrected prior to the NCHD inspection on March 2, 1987.

NUS Region 2 FIT conducted a nonsampling site inspection of the Autotronic Products Site on September 3, 1987, to confirm current on-site conditions. There were no readings above background levels detected on the HNu photoionization detector. The OVA flame ionization detector received readings above background in the vicinity of the building.

Ref. Nos. 1, 2, 8, 9, 10, 21, 22, 23

SECTION 2

ENVIRONMENTAL PROTECTION AGENCY FORM 2070-13

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

2. SITE NAME AND LOCATION

SITE NAME (Legal, common, or descriptive name of site) 02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER
Autotronic Products 3300 Lawson Boulevard
CITY 04 STATE 05 ZIP CODE 06 COUNTY 07 COUNTY 08 CONG DIST.
Oceanside NY 11572 Nassau CODE 059 5
COORDINATES
LATITUDE LONGITUDE
4 00 3 7' 4 6" N 0 7 30 3 9' 1 3" W
10 TYPE OF OWNERSHIP (Check one)
X A. PRIVATE B. FEDERAL C. STATE
D. COUNTY E. MUNICIPAL F. OTHER
G. UNKNOWN

3. INSPECTION INFORMATION

DATE OF INSPECTION 02 SITE STATUS 03 YEARS OF OPERATION
09 / 03 / 87 X ACTIVE 1981 / Present UNKNOWN
MONTH DAY YEAR INACTIVE BEGINNING YEAR ENDING YEAR
AGENCY PERFORMING INSPECTION (Check all that apply)
A. EPA X B. EPA CONTRACTOR NUS Corp. Region 2 FIT C. MUNICIPAL D. MUNICIPAL CONTRACTOR
(Name of firm) (Name of firm)
E. STATE F. STATE CONTRACTOR G. OTHER (Specify)
(Name of firm)

04 CHIEF INSPECTOR 06 TITLE 07 ORGANIZATION 08 TELEPHONE NO.
William Schnitzerling Environmental Scientist NUS Corp. (201) 225-6160
OTHER INSPECTORS 10 TITLE 11 ORGANIZATION 12 TELEPHONE NO.
John Ducar Geologist NUS Corp. (201) 225-6160
Brian Pedersen Chemical Engineer NUS Corp. (201) 225-6160

13 SITE REPRESENTATIVES INTERVIEWED 14 TITLE 15 ADDRESS 16 TELEPHONE NO.
Mr. Joseph Spadafina President of 3300 Lawson Blvd (516) 536-6765
Autotronic Products Oceanside, NY

17 ACCESS GAINED BY 18 TIME OF INSPECTION 19 WEATHER CONDITIONS
(Check one)
PERMISSION 0900 Sunny, 75°, wind north 5-8 mph
WARRANT

20 INFORMATION AVAILABLE FROM
CONTACT 02 OF (Agency/Organization) 03 TELEPHONE NO.
Amy Brochu U.S. EPA (201) 906-6802

21 PERSON RESPONSIBLE FOR SITE INSPECTION FORM 05 AGENCY 06 ORGANIZATION 07 TELEPHONE NO. 08 DATE
Jennifer O. Leahy Region 2 FIT NUS Corp. (201) 225-6160 10 / 05 / 90

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 2 - WASTE INFORMATION

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

WASTE STATES, QUANTITIES, AND CHARACTERISTICS

PHYSICAL STATES (Check all that apply)		02 WASTE QUANTITY AT SITE	03 WASTE CHARACTERISTICS (Check all that apply)		
SOLID	E. SLURRY	(Measures of waste quantities must be independent)	X A. TOXIC	E. SOLUBLE	X I. HIGHLY VOLATILE
POWDER, FINES	F. LIQUID		B. CORROSIVE	F. INFECTIOUS	J. EXPLOSIVE
G. SLUDGE	G. GAS		C. RADIOACTIVE	G. FLAMMABLE	K. REACTIVE
OTHER			D. PERSISTENT	H. IGNITABLE	L. INCOMPATIBLE
(Specify)		TONS			M. NOT APPLICABLE
		CUBIC YARDS			
		NO. OF DRUMS	one		

WASTE TYPE CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE			
LW	OILY WASTE			
SOL	SOLVENTS	50	gallons	Spent 1,1,1-trichloroethane dumped on site in 1 - quart batches between 1981 and 1982.
PSD	PESTICIDES			
OC	OTHER ORGANIC CHEMICALS			
IOC	INORGANIC CHEMICALS			
CD	ACIDS			
BAS	BASES			
ES	HEAVY METALS			

HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

CATEGORY	02 SUBSTANCE NAME	03 CAS NUMBER	04 STORAGE/DISPOSAL METHOD	05 CONCENTRATION	06 MEASURE OF CONCENTRATION
SOL	1,1,1-trichloroethane	71-55-6	Dumped in back of site on paved area.	Unknown	Unknown

FEEDSTOCKS (See Appendix for CAS Numbers)

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS	1,1,1-trichloroethane	71-55-6	FDS		
FDS	Flux	999	FDS		
FDS	Acetone	67-64-1	FDS		
FDS	Paint thinners	999	FDS		

SOURCES OF INFORMATION (See specific references. e.g., state files, sample analysis, reports)

Preliminary Assessment Report for Autotronic Products, E.A. Science and Technology, Middletown, New York, 1986.
Field Notebook No. 0133, Autotronic Products, TOD No. 02-8708-02, Site Inspection, NUS Corporation, Region 2 FIT, Edison, New Jersey, September 3, 1987.
Telecon Note: Conversation between Rocky Piaggione, New York State Department of Environmental Conservation, and William Schnitzerling, NUS Corp., August 5, 1987.
Telecon Note: Conversation between Joe Schechter, Nassau County, Division of Health, and William Schnitzerling, NUS Corp., August 5, 1987.
Chemical/Solvent Waste Report, Bureau of Land Resources Management, Nassau County Health Department. Permit Number 295.

NY 2070-13 (7-8)

02-8708-02-SR
Rev. No. 0

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

1. HAZARDOUS CONDITIONS AND INCIDENTS

1 X A. GROUNDWATER CONTAMINATION 02 OBSERVED (DATE:) X POTENTIAL ALLEGED
3 POPULATION POTENTIALLY AFFECTED: 149,400 04 NARRATIVE DESCRIPTION

There is potential for groundwater contamination. Autotronic Products dumped approximately 50 gallons of 1,1,1-trichloroethane onto a paved section of the back of its property. If the waste migrated off site into the downgradient, unpaved property owned by the Long Island Railroad, it had the potential to leach into the groundwater contaminating the upper glacial and the Magothy Aquifers. These aquifers are hydraulically connected. The upper glacial aquifer is used for irrigation and the Magothy is used for drinking purposes.

1 X B. SURFACE WATER CONTAMINATION 02 OBSERVED (DATE:) X POTENTIAL ALLEGED
3 POPULATION POTENTIALLY AFFECTED: 149,400 04 NARRATIVE DESCRIPTION

There is a potential for surface water contamination. Approximately 50 gallons of 1,1,1-trichloroethane was dumped onto a paved section in the back of the property. Waste migrated off site in the direction of Reed Channel located 0.1 mile west of the site. Reed Channel is used for recreational purposes.

1 C. CONTAMINATION OF AIR 02 OBSERVED (DATE:) POTENTIAL ALLEGED
3 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION

There is no potential for air contamination. Autotronic Products presently employs proper waste management practices.

1 D. FIRE/EXPLOSIVE CONDITIONS 02 OBSERVED (DATE:) POTENTIAL ALLEGED
3 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION

The site inspection conducted by NUS Corp. Region 2 FIT did not indicate the potential for fire or explosion.

1 E. DIRECT CONTACT 02 OBSERVED (DATE:) POTENTIAL ALLEGED
3 POPULATION POTENTIALLY AFFECTED: 04 NARRATIVE DESCRIPTION

The site inspection conducted by NUS Region 2 FIT did not indicate the potential for direct contact. The illegal dumping has ceased and the wastes are now properly managed, according to the NCHD.

1 X F. CONTAMINATION OF SOIL 02 OBSERVED (DATE:) X POTENTIAL ALLEGED
3 AREA POTENTIALLY AFFECTED: 0.04 (ACRES) 04 NARRATIVE DESCRIPTION

The area where the waste was dumped is paved. The soil that may have been contaminated by waste migrating from Autotronic Products is the downslope, unpaved Long Island Railroad property bordering the back of the site.

1 G. DRINKING WATER CONTAMINATION 02 OBSERVED (DATE:) X POTENTIAL ALLEGED
3 POPULATION POTENTIALLY AFFECTED: 149,400 04 NARRATIVE DESCRIPTION

Waste migrating from Autotronic Products has the potential to contaminate the upper glacial aquifer. Since there is a hydraulic connection between the upper glacial and the Magothy aquifers, there is a limited potential for drinking water contamination. The depth to the Magothy aquifer is 500 feet.

1 X H. WORKER EXPOSURE/INJURY 02 OBSERVED (DATE:) X POTENTIAL ALLEGED
3 WORKERS POTENTIALLY AFFECTED: 20 04 NARRATIVE DESCRIPTION

Although Autotronic Products is in compliance with its hazardous waste permits, workers may be exposed or injured when managing the 1,1,1-trichloroethane. The waste is stored in the back of the warehouse. Access is restricted to authorized personnel.

1 I. POPULATION EXPOSURE/INJURY 02 OBSERVED (DATE:) POTENTIAL ALLEGED
3 POPULATION POTENTIALLY AFFECTED: 149,400 04 NARRATIVE DESCRIPTION

There is a limited potential for drinking water contamination due to the depth of the Magothy aquifer. Nearby surface waters are used for recreational purposes.

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

J. DAMAGE TO FLORA
NARRATIVE DESCRIPTION

02 _ OBSERVED (DATE: _____) _ POTENTIAL _ ALLEGED

It is unlikely that there would be damage to flora. The 1,1,1-trichloroethane was illegally dumped on the pavement in small quantities. In addition, the site is located in a commercial/industrial area.

K. DAMAGE TO FAUNA

NARRATIVE DESCRIPTION (Include name(s) of species)

02 _ OBSERVED (DATE: _____) _ POTENTIAL _ ALLEGED

It is unlikely that there would be any damage to fauna. The 1,1,1-trichloroethane was illegally dumped on the pavement in small quantities. In addition, the site is located in a commercial/industrial area.

L. CONTAMINATION OF FOOD CHAIN
NARRATIVE DESCRIPTION

02 _ OBSERVED (DATE: _____) _ POTENTIAL _ ALLEGED

It is unlikely that contamination of the food chain would occur because the 1,1,1-trichloroethane is only slightly bioaccumulative and has an elimination half-life of 2 days.

M. UNSTABLE CONTAINMENT OF WASTES

(Spills/runoff/standing liquids/leaking drums)

POPULATION POTENTIALLY AFFECTED: 149,000

02 X OBSERVED (DATE: 1981-1982) _ POTENTIAL _ ALLEGED

04 NARRATIVE DESCRIPTION

1,1,1-trichloroethane was illegally dumped in 1-quart batches behind the facility from 1981 to 1982. As of September 1987, the wastes were properly stored inside the warehouse in accordance with Nassau County Health Department regulations.

N. DAMAGE TO OFFSITE PROPERTY
NARRATIVE DESCRIPTION

02 _ OBSERVED (DATE: _____) X POTENTIAL _ ALLEGED

There is a potential that off-site property may have been damaged by the 1,1,1-trichloroethane that was illegally dumped. The contaminant may have migrated off site to the downgradient property owned by Long Island Railroad.

O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTs
NARRATIVE DESCRIPTION

02 _ OBSERVED (DATE: _____) _ POTENTIAL _ ALLEGED

There is no potential for contamination of sewers, storm drains, and WWTs. When the 1,1,1-trichloroethane was illegally dumped, it did not come into contact with storm drains or sewers. The present storage area contains a spill control system to prevent waste migration.

P. ILLEGAL/UNAUTHORIZED DUMPING
NARRATIVE DESCRIPTION

02 X OBSERVED (DATE: 1981 - 1982) _ POTENTIAL _ ALLEGED

Between 1981 and early 1982, an estimated 50 gallons of 1,1,1-trichloroethane were illegally dumped on the paved section of the property behind Autotronic Products. This practice ceased in 1982.

DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

None

TOTAL POPULATION POTENTIALLY AFFECTED: 149,400

COMMENTS

Since being fined for illegally dumping approximately 50 gallons of TCA, Autotronic Products has been reporting to the Nassau County Health Department. Any recorded violations of the permits have been minor and corrected to the satisfaction of NCHD. According to the health department, 1,1,1-trichloroethane is the only suspected hazardous waste at this site.

SOURCES OF INFORMATION (Cite specific references. e.g., state files, sample analysis, reports)

Project Note: From W. Schnitzerling, to Autotronic Products File, Subject: Groundwater usage near the site, September 4, 1987.
Telecon Note: Conversation between Joe Schecter, Nassau County Division of Health, and William Schnitzerling, NUS Corp., August 5, 1987.
Telecon Note: Conversation between Rocky Piaggione, New York State Department of Environmental Conservation, and William Schnitzerling, NUS Corp., August 5, 1987.
Field Notebook No. 0133, Autotronic Products, TDD No. 02-8708-02, Site Inspection, NUS Corporation, Region 2 FIT, Edison, New Jersey, September 3, 1987.
Preliminary Assessment Report of Autotronic Products, E.A. Science and Technology, 1986.
Telecon Note: Conversation between Don Myott, Nassau County Health Department, Pure Waters Division, and S. Shulfer, NUS Corporation, May 10, 1988.
General Sciences Corporation, Graphic Exposure Modeling System (GEMS) Landover, Maryland, 1986.
New York State Department of Environmental Conservation, Wildlife Resource Center, "Significant Coastal Fish and Wildlife Habitat, West Hempstead Bay," "Significant Coastal Fish and Wildlife Habitat, Middle Hempstead Bay," and "Significant Coastal Fish and Wildlife Habitat, Nassau Beach," Delmar, New York, 1987.
Chemical, physical, and biological properties of compounds present at hazardous waste sites. Final report prepared for the U.S. Environmental Protection Agency, Clement Associates, Inc., September 1985.
New York State Atlas of Community Water System Sources, New York State Department of Health, 1982.
Soren, Julian. Results of subsurface exploration in the mid-island area of western Suffolk County, Long Island, New York. Long Island Water Resources, Bulletin No. 1, 1971.

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPDES				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPCC PLAN				
<input type="checkbox"/> G. STATE (Specify)				

X H. LOCAL (Specify) County 295

X I. OTHER (Specify) Article XI
Solid Waste Management Facility Permit 109
X J. NONE

Chemical Inventory Permit to
operate a toxic or hazardous
materials storage facility;
Permit to store hazardous
materials on site.

WASTE DESCRIPTION

01 Storage/Disposal (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input type="checkbox"/> A. SURFACE IMPOUNDMENT			<input type="checkbox"/> A. INCINERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> B. UNDERGROUND INJECTION	Adjacent
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	06 AREA OF SITE
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	0.04
<input type="checkbox"/> H. OPEN DUMP			<input checked="" type="checkbox"/> H. OTHER N/A (Specify)	(Acres)
X I. OTHER Spill (Specify)	50	Gallons		

COMMENTS

The only reported incident at this site is the dumping of approximately 50 gallons of 1,1,1-trichloroethane on the paved area behind the facility. It was dumped in 1-quart batches between 1981 and 1982. The 1,1,1-trichloroethane is believed to have run off the western boundary of Autotronic's property onto the unpaved land owned by the Long Island Railroad. The waste may have leached into the groundwater.

Currently, waste is collected in a 55-gallon drum and transported off site by licensed haulers on an as-needed basis. Autotronic Products produces less than 1 drum of waste a year. Because such a low volume of waste is produced, Autotronic Products is in the process of petitioning the NCHD for a change in its hazardous waste management permits. This facility is regularly inspected by the NCHD, and there are no complaints or violations on file with local or state officials.

CONTAINMENT

CONTAINMENT OF WASTES (Check one)

☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☐ C. INADEQUATE, POOR ☒ D. INSECURE, UNSOUND, DANGEROUS

DESCRIPTION OF DRUMS, DYKING, LINERS, BARRIERS, ETC.

The waste was dumped directly onto a paved surface which had no diversion system. At present, Autotronic Products generates less than 1 drum of waste a year. The 55-gallon drum is stored on a pallet in the warehouse in a secured area. The last inspection of the waste storage area was March 2, 1987, and no violations were noted.

ACCESSIBILITY

WASTE EASILY ACCESSIBLE: ☐ YES ☒ NO

COMMENTS

The waste storage shed is not easily accessible. Wastes are stored on pallets in an enclosed area that is locked.

SOURCES OF INFORMATION (Cite specific references. e.g., state files, sample analysis, reports)

Nassau County Department of Health, Solid Waste Management Facility Permits, No. 109, February 6, 1984 and No. 295, February 7, 1985.

Telecon Note: Conversation between Joe Schecter, Nassau County Division of Health, and William Schnitzerling, NUS Corp, August 5, 1987.

Field Notebook No. 0133, Autotronic Products, TDD No. 02-8708-02, Site Inspection, NUS Corporation Region 2 FIT, Edison, New Jersey, September 3, 1987.

Preliminary Assessment Report of Autotronic Products, E.A. Science and Technology, March 24, 1986.

Letter from Joseph M. Spadefina, President Autotronic Products, to Mr. Schaefer, Nassau County Department of Health, June 24, 1987.

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

2. ENVIRONMENTAL INFORMATION

PERMEABILITY OF UNSATURATED ZONE (Check one)

A. 10^{-6} - 10^{-8} cm/sec ☒ B. 10^{-4} - 10^{-6} cm/sec ☐ C. 10^{-4} - 10^{-3} cm/sec ☐ D. GREATER THAN 10^{-3} cm/sec

PERMEABILITY OF BEDROCK (Check one)

☒ A. IMPERMEABLE
(Less than 10^{-6} cm/sec) ☐ B. RELATIVELY IMPERMEABLE
(10^{-4} - 10^{-6} cm/sec) ☐ C. RELATIVELY PERMEABLE
(10^{-2} - 10^{-4} cm/sec) ☐ D. VERY PERMEABLE
(Greater than 10^{-2} cm/sec)

DEPTH TO BEDROCK

04 DEPTH OF CONTAMINATED SOIL ZONE

05 SOIL pH

2,700 (ft) Unknown (ft) Unknown

NE PRECIPITATION

07 ONE YEAR 24 HOUR RAINFALL

08 SLOPE
SITE SLOPE

DIRECTION OF SITE SLOPE

TERRAIN AVERAGE SLOPE

14 (in) 2.75 (in) 1 % West 1 %

FLOOD POTENTIAL

10

SITE IS IN 100 YEAR FLOODPLAIN SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

DISTANCE TO WETLANDS (5 acre minimum)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

ESTUARINE

OTHER

> 1 (mi)

A. 0.75 (mi) B. > 1 (mi)

ENDANGERED SPECIES: Not Applicable

LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS: NATIONAL/STATE PARKS,
FORESTS, OR WILDLIFE RESERVES

PRIME AG LAND

AGRICULTURAL LANDS

AG LAND

A. .002 (mi) B. 0.04 mile to Residential (mi)
2 miles to Wildlife Reserve C. > 2 (mi) D. > 1 (mi)

DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

Most of the area behind the Autotronic Products building is paved, having a very slight slope to the west. This slope leads to the railroad tracks owned by the Long Island Railroad. The topography of the area surrounding this site (Ganside, New York) is generally level. The land gently slopes towards the tidal channels south of Autotronic Products.

SOURCES OF INFORMATION (Cite specific references e.g., state files, sample analysis, reports)

New York State Department of Health, New York State Atlas of Community Water System Sources, 1982.
Telecon Note: Conversation between Joe Schechter, Nassau County Division of Health, and William Schnitzerling, NUS Corp., August 5, 1987.
Telecon Note: Conversation between Rocky Piaggione, New York State Department of Environmental Conservation, and William Schnitzerling, NUS Corp., August 5, 1987.
Field Notebook No. 0133, Autotronic Products, TOD No. 02-8708-02, Site Inspection, NUS Corporation, Region 2 FIT, Edison, New Jersey, September 3, 1987.
U.S. Department of Agriculture, Soil Conservation Service, Important Farmland of New York, 1977.
Federal Emergency Management Agency, Flood Insurance Rate Map, Town of Hempstead, NY, Community Panel No. 3604670051B, 1985.
Preliminary Assessment Report of Autotronic Products, EA Science and Technology, March 24, 1986.
New York State Department of Environmental Conservation, Wildlife Resource Center, "Significant Coastal Fish and Wildlife Habitat, West Hempstead Bay," "Significant Coastal Fish and Wildlife Habitat, Middle Hempstead Bay," and "Significant Coastal Fish and Wildlife Habitat, Nassau Beach," Delmar, New York, 1987.
U.S. Geological Survey, Hydrogeology of the Town of North Hempstead, Nassau County, Long Island, New York. Long Island Water Resources Bulletin 12.
Kimmel, Grant E., et al. Analog model prediction of the hydrologic effects of sanitary sewerage in southeast Nassau and southwest Suffolk Counties, New York. Long Island Water Resources Bulletin LIW-6, 1977.
Uncontrolled hazardous waste site ranking system, A user's manual, 40 CFR, Part 300, Appendix A, 1986.
Project Note: From W. Schnitzerling, to Autotronic Products file, Subject: Groundwater usage near site, September 4, 1987.
General Sciences Corporation, Graphic Exposure Modeling System (GEMS), Landover, Maryland, 1986.
Three Mile Vicinity Map based on U.S. Department of the Interior, Geological Survey Topographic Maps, 7.5 minute series, Quadrangles of "Lynbrook, NY," "Lawrence, NY," and "Freeport, NY," 1969.
Soren, Julian. Results of subsurface exploration in the mid-island area of Western Suffolk County, Long Island, New York. Long Island Water Resources, Bulletin No. 1, 1971.
Atlantic Coast Ecological Inventory, New York, NY-Conn-NJ, U.S. Fish and Wildlife Service, 1980.

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - DEMOGRAPHIC, AND ENVIRONMENTAL DATA

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

DRINKING WATER SUPPLY TYPE OF DRINKING SUPPLY (Check as applicable)		02 STATUS			03 DISTANCE TO SITE	
	SURFACE A. <input type="checkbox"/> C. <input type="checkbox"/>	WELL B. <input checked="" type="checkbox"/> D. <input type="checkbox"/>	ENDANGERED A. <input type="checkbox"/> D. <input type="checkbox"/>	AFFECTED B. <input type="checkbox"/> E. <input type="checkbox"/>	MONITORED C. <input type="checkbox"/> F. <input type="checkbox"/>	
COMMUNITY I-COMMUNITY						A. 1.5 (mi) B. 0 (mi)

G. GROUNDWATER
GROUNDWATER USE IN VICINITY (Check one)

A. ONLY SOURCE FOR DRINKING ☒ B. DRINKING ☐ C. COMMERCIAL, INDUSTRIAL, IRRIGATION ☐ D. NOT USED, UNUSEABLE ☐

(Other sources available) (Limited other sources available)
COMMERCIAL,
INDUSTRIAL,
IRRIGATION
(No other water sources available)

POPULATION SERVED BY GROUND WATER: 149,400 03 DISTANCE TO NEAREST DRINKING WATER WELL: 1.5 (mi)

DEPTH TO GROUNDWATER	05 DIRECTION OF GROUNDWATER FLOW	06 DEPTH TO AQUIFER OF CONCERN	07 POTENTIAL YIELD OF AQUIFER	08 SOLE SOURCE AQUIFER
5 (ft)	South	500 (ft)	Unknown (gpd)	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO

DESCRIPTION OF WELLS (Including usage, depth, and location relative to population and buildings)

There are three aquifers underlying the site: the upper glacial, the Magothy, and the Lloyd aquifers. The upper glacial and Magothy are hydraulically connected. The upper glacial aquifer is used primarily for irrigation purposes. This aquifer consists of glacial deposits of stratified sand and gravel in multiwater spillways and outwash plains. This aquifer varies in thickness from 100 to 400 feet. The Magothy aquifer consists of beds and lenses of fine and coarse sand containing traces to large amounts of clay and silt intercolated with thick to thin siltstone lenses of clay, silt, and clayey silty sand. The aquifer's depth in this area varies from 500 to 7,000 feet and is the sole source of water for potable purposes in the area. The Lloyd aquifer is located beneath the Magothy; at this time this aquifer is not used. Bedrock is composed of crystalline metamorphic and various rocks such as schist, gneiss, and granite. The soft clayey zone within bedrock is more than 100 feet thick. The actual depth of bedrock is from the surface to 2,700 feet.

RECHARGE AREA		11. DISCHARGE AREA	
YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>	COMMENTS	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>	COMMENTS The area around this site is a groundwater discharge area for the upper glacial aquifer.

12. SURFACE WATER
SURFACE WATER USE (Check one)

☒ A. RESERVOIR, RECREATION DRINKING WATER SOURCE ☐ B. IRRIGATION, ECONOMICALLY IMPORTANT RESOURCES ☐ C. COMMERCIAL, INDUSTRIAL ☐ D. NOT CURRENTLY USED

AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME:	AFFECTED	DISTANCE TO SITE
Reed Channel	Unknown	0.10 (mi)
Hog Island Channel	Unknown	0.20 (mi)
East Rockaway Channel	Unknown	0.40 (mi)
Hewlett Bay	Unknown	0.60 (mi)

13. DEMOGRAPHIC AND PROPERTY INFORMATION

TOTAL POPULATION WITHIN			02 DISTANCE TO NEAREST POPULATION
ONE (1) MILE OF SITE	TWO (2) MILES OF SITE	THREE (3) MILES OF SITE	
A. 13,200 NO. OF PERSONS	B. 63,900 NO. OF PERSONS	C. 149,400 NO. OF PERSONS	0.02 (mi)

NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE: Approx. 21,400 04 DISTANCE TO NEAREST OFF-SITE BUILDING: 0.02 (mi)

POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site. e.g., rural, village, densely populated urban area)

Autronic Products is located in a moderately populated section of Oceanside, New York. The area of the site has mixed residential and commercial/industrial uses.

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER			
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
PILL			
SOIL			
VEGETATION			
OTHER	No samples were collected.		

II. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS
Monitoring	No readings above background conditions were detected around the outside of the facility, on the organic vapor analyzer (OVA) flame ionization detector or the HNu photoionization detector. However, a reading of 5 ppm was detected inside the warehouse on the OVA.

III. PHOTOGRAPHS AND MAPS

01 TYPE	X GROUND	AERIAL	02 IN CUSTODY OF
			NUS Corporation Region 2 FIT (Name of organization or individual)

03 MAPS	04 LOCATION OF MAPS
YES NO	NUS Corporation Region 2 FIT, Edison, New Jersey

IV. OTHER FIELD DATA COLLECTED (Provide narrative description)

Field Notebook No. 0133, Autotronic Products, TDD No. 02-8708-02, Site Inspection, NUS Corp. Region 2 FIT, Edison, NJ, September 3, 1987.

V. SOURCES OF INFORMATION (Cite specific references. e.g., state files, sample analysis, reports)

Field Notebook No. 0133, Autotronic Products, TDD No. 02-8708-02, Site Inspection, NUS Corporation, Region 2 FIT, Edison, New Jersey, September 3, 1987.
Three Mile Vicinity Map based on U.S. Department of the Interior, Geological Survey Topographic Maps, 7.5 minute series, Quadrangles of "Lynbrook, NY," "Lawrence, NY," and "Freeport, NY," 1969.

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

I. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

CURRENT OWNER(S)		PARENT COMPANY (If applicable)			
NAME	02 D + B NUMBER	08 NAME	09 D + B NUMBER		
Joseph Spadafina STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD#, etc.)	11 SIC CODE		
33 Lawson Boulevard CITY	06 STATE	07 ZIP CODE	12 CITY	13 STATE	14 ZIP CODE
Oceanside	NY	11572			
NAME	02 D + B NUMBER	08 NAME	09 D + B NUMBER		
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD#, etc.)	11 SIC CODE		
CITY	06 STATE	07 ZIP CODE	12 CITY	13 STATE	14 ZIP CODE
NAME	02 D + B NUMBER	08 NAME	09 D + B NUMBER		
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD#, etc.)	11 SIC CODE		
CITY	06 STATE	07 ZIP CODE	12 CITY	13 STATE	14 ZIP CODE
NAME	02 D + B NUMBER	08 NAME	09 D + B NUMBER		
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD#, etc.)	11 SIC CODE		
CITY	06 STATE	07 ZIP CODE	12 CITY	13 STATE	14 ZIP CODE
NAME	02 D + B NUMBER	08 NAME	09 D + B NUMBER		
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	10 STREET ADDRESS (P.O. Box, RFD#, etc.)	11 SIC CODE		
CITY	06 STATE	07 ZIP CODE	12 CITY	13 STATE	14 ZIP CODE

PREVIOUS OWNER(S) (List most recent first)			IV. REALTY OWNER(S) (If applicable; list most recent first)		
NAME	02 D + B NUMBER	01 NAME	02 D + B NUMBER		
Union Corporation STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE		
CITY	06 STATE	05 CITY	06 STATE	07 ZIP CODE	
Verona	PA				
NAME	02 D + B NUMBER	01 NAME	02 D + B NUMBER		
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE		
CITY	06 STATE	05 CITY	06 STATE	07 ZIP CODE	
NAME	02 D + B NUMBER	01 NAME	02 D + B NUMBER		
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE		
CITY	06 STATE	05 CITY	06 STATE	07 ZIP CODE	

SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Preliminary Assessment Report of Autotronic Products, EA Science and Technology, March 24, 1986.

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

CURRENT OPERATOR(S)		OPERATOR'S PARENT COMPANY (If applicable)			
NAME	02 D + B Number	10 NAME	11 D + B NUMBER		
Autotronic Products					
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	12 STREET ADDRESS (P.O. Box, RFD#, etc.)	13 SIC CODE		
3300 Lawson Blvd.					
CITY	06 STATE	07 ZIP CODE	14 CITY	15 STATE	16 ZIP CODE
Oceanside	NY	11572			
YEARS OF OPERATION	09 NAME OF OWNER				
8	J. Spadafina				

PREVIOUS OPERATOR(S) (List most recent first: Provide only if different from owner)		PREVIOUS OPERATOR'S PARENT COMPANIES (If applicable)			
NAME	02 D + B Number	10 NAME	11 D + B NUMBER		
Autotronics Inc.		Union Corporation			
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	12 STREET ADDRESS (P.O. Box, RFD#, etc.)	13 SIC CODE		
3300 Lawson Blvd.					
CITY	06 STATE	07 ZIP CODE	14 CITY	15 STATE	16 ZIP CODE
Oceanside	NY	11572	Verona	PA	
YEARS OF OPERATION	09 NAME OF OWNER				
Approx. 17	Union Corporation				

NAME	02 D + B Number	10 NAME	11 D + B NUMBER		
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	12 STREET ADDRESS (P.O. Box, RFD#, etc.)	13 SIC CODE		
CITY	06 STATE	07 ZIP CODE	14 CITY	15 STATE	16 ZIP CODE
YEARS OF OPERATION	09 NAME OF OWNER				

NAME	02 D + B Number	10 NAME	11 D + B NUMBER		
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	12 STREET ADDRESS (P.O. Box, RFD#, etc.)	13 SIC CODE		
CITY	06 STATE	07 ZIP CODE	14 CITY	15 STATE	16 ZIP CODE
YEARS OF OPERATION	09 NAME OF OWNER				

SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)
Preliminary Assessment Report of Autotronic Products, EA Science and Technology, March 24, 1986.

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

ON-SITE GENERATOR

NAME	02 D + B NUMBER
Autotronic Products	
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE
3300 Lawson Blvd.	
CITY	06 STATE 07 ZIP CODE
Oranston	NY 11572

OFF-SITE GENERATOR(S)

NAME	02 D + B NUMBER	01 NAME	02 D + B NUMBER
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE
CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

NAME	02 D + B NUMBER	01 NAME	02 D + B NUMBER
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE
CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

TRANSPORTER(S)

NAME	02 D + B NUMBER	01 NAME	02 D + B NUMBER
Chemical Pollution Control			
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE
120 South Fourth Street			
CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
Babylon Shore	NY 11706		

NAME	02 D + B NUMBER	01 NAME	02 D + B NUMBER
Pride Solvents			
STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD#, etc.)	04 SIC CODE
78-88 Larmar Street			
CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
W. Babylon	NY 11704		

SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Chemical/Solvent Waste Report for Autotronic Products, Shipped by Pride Solvents, November 26, 1984.
Chemical/Solvent Waste Report for Autotronic Products, Shipped by Chemical Pollution, June 7, 1985.

PAST RESPONSE ACTIVITIES

A. WATER SUPPLY CLOSED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
B. TEMPORARY WATER SUPPLY PROVIDED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
C. PERMANENT WATER SUPPLY PROVIDED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
D. SPILLED MATERIAL REMOVED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
E. CONTAMINATED SOIL REMOVED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
F. WASTE REPACKAGED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
G. WASTE DISPOSED ELSEWHERE DESCRIPTION	02 DATE: _____	03 AGENCY: _____
Waste is now properly stored, and it is hauled off site on an as-needed basis by licensed hazardous waste scavengers.		
H. ON SITE BURIAL DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
I. IN SITU CHEMICAL TREATMENT DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
J. IN SITU BIOLOGICAL TREATMENT DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
K. IN SITU PHYSICAL TREATMENT DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
L. ENCAPSULATION DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
M. EMERGENCY WASTE TREATMENT DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
N. CUTOFF WALLS DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
O. EMERGENCY DIKING/SURFACE WATER DIVERSION DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
P. CUTOFF TRENCHES/SUMP DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
Q. SUBSURFACE CUTOFF WALL DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY D981184211

PAST RESPONSE ACTIVITIES

R. BARRIER WALLS CONSTRUCTED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
S. CAPPING/COVERING DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
T. BULK TANKAGE REPAIRED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
U. GROUT CURTAIN CONSTRUCTED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
V. BOTTOM SEALED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
W. GAS CONTROL DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
X. FIRE CONTROL DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
Y. LEACHATE TREATMENT DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
Z. AREA EVACUATED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
1. ACCESS TO SITE RESTRICTED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
2. POPULATION RELOCATED DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		
3. OTHER REMEDIAL ACTIVITIES DESCRIPTION	02 DATE: _____	03 AGENCY: _____
No previous history.		

SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Preliminary Assessment Report of Autotronic Products, EA Science and Technology, March 24, 1986.
Telephone Note: Conversation between Joe Schecter, Nassau County Division of Health, and William Schnitzerling, NUS Corp., August 5, 1987.
Telephone Note: Conversation between Rocky Piaggione, New York State Department of Environmental Conservation, and William Schnitzerling, NUS Corp., August 5, 1987.
Field Notebook No. 0133, Autotronic Products, TDD No. 02-8708-02, Site Inspection, NUS Corporation Region 2 FIT, Edison, New Jersey, September 3, 1987.

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
NY 0981184211

ENFORCEMENT INFORMATION

PAST REGULATORY/ENFORCEMENT ACTION ☒ YES ☐ NO

DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

Autotronic Products was fined \$1,000 by the NYSDEC for illegally disposing of 1,1,1-trichloroethane in the back of its property between 1981 and 1982. Since this practice ceased in 1982, Autotronic Products has been in compliance with its state and county hazardous waste management permits.

SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, report)

Preliminary Assessment Report of Autotronic Products, EA Science and Technology, March 24, 1986.
Telecon Note: Conversation between Joe Schechter, Nassau County Division of Health, and William Schnitzerling, NUS Corp., August 5, 1987.
Telecon Note: Conversation between Rocky Piaggione, New York State Department of Environmental Conservation, and William Schnitzerling, NUS Corp., August 5, 1987.
Field Notebook No. 0133, Autotronic Products, TDD No. 02-8708-02, Site Inspection, NUS Corporation, Region 2 FIT, Edison, New Jersey, September 3, 1987.
NYSDEC Memorandum: From Rocky J. Piaggione, to Al Machlin, Subject: Autotronic Products Inc., May 23, 1983.

SECTION 3


MAPS AND PHOTOGRAPHS

MAPS

**AUTOTRONIC PRODUCTS
OCEANSIDE, NEW YORK**

Contents

- Figure 1: Site Location Map**
Figure 2: Site Map




(QUAD) LYNBROOK, N.Y.

SITE LOCATION MAP
AUTOTRONIC PRODUCTS, OCEANSIDE, N.Y.

SCALE: 1" = 2000'

FIGURE 1





SITE MAP
AUTOTRONIC PRODUCTS, OCEANSIDE, N.Y.
(NOT TO SCALE)

SECTION 4

CONCLUSIONS AND RECOMMENDATIONS

CONCLUSIONS AND RECOMMENDATIONS

Between 1981 and 1982, Autotronic Products illegally dumped less than 50 gallons of 1,1,1-trichloroethane in 1-quart batches on the pavement in the rear of the facility. It is not known if the waste evaporated or ran off the pavement onto the adjacent property owned by the Long Island Railroad. Autotronic Products now operates under strict permits issued by the NYSDEC and NCHD and was found to be in compliance as of March 2, 1987.

A recommendation of **NO FURTHER REMEDIAL ACTION PLANNED** under CERCLA/SARA is given for the Autotronic Products site. This recommendation is based on the following information that was acquired during the site inspection and subsequent report preparation:

- There was a small quantity of hazardous waste released during a limited period of time. This practice was discontinued and Autotronic Products now employs proper waste management practices.
- There is no surface water intake used for potable or irrigation purposes within 3 miles downstream of the site.
- The 1,1,1-trichloroethane was released on a paved surface in small quantities, and the depth to the aquifer of concern is 500 feet. There is little likelihood of migration of contaminants to the source of potable water.
- Since proper waste management practices are now employed and the site is secure with access limited to authorized personnel, there is no threat of direct contact with hazardous waste.

SECTION 5

BIBLIOGRAPHY OF INFORMATION SOURCES

BIBLIOGRAPHY OF INFORMATION SOURCES

1. Preliminary Assessment Report of Autotronic Products, E.A. Science and Technology, March 24, 1986.
2. Field Notebook No. 0133, Autotronic Products, TDD No. 02-8708-02, Site Inspection, NUS Corporation Region 2 FIT, Edison, New Jersey, September 3, 1987.
3. U.S. Geological Survey, Hydrogeology of the Town of North Hempstead, Nassau County, Long Island, New York. Long Island Water Resources Bulletin 12, 1979.
4. Kimmel, Grant E., et al. Analog model prediction of the hydrologic effects of sanitary sewerage in southeast Nassau and southwest Suffolk Counties, New York, Long Island Water Resources Bulletin LIWR-6, 1977.
5. Uncontrolled hazardous waste site ranking system, A user's manual, 40 CFR, Part 300, Appendix A, 1986.
6. Telecon Note: Conversation between Rocky Piaggione, Attorney for the Enforcement Division, New York State Department of Environmental Conservation, and W. Schnitzerling, NUS Corporation, August 5, 1987.
7. Telecon Note: Conversation between Joseph Schechter, Nassau County Health Department, and W. Schnitzerling, NUS Corporation, August 5, 1987.
8. New York State Department of Health, New York State Atlas of Community Water System Sources, 1982
9. Three Mile Vicinity Map based on U.S. Department of the Interior Geological Survey Topographic Maps, 7.5 minute series, Quadrangles of "Lynbrook, NY," "Lawrence, NY," and "Freeport, NY," 1969.
10. N.Y. State Department of Environmental Conservation, Wildlife Resource Center, "Significant Coastal Fish and Wildlife Habitat, West Hempstead Bay," "Significant Coastal Fish and Wildlife Habitat, Middle Hempstead Bay," and "Significant Coastal Fish and Wildlife Habitat, Nassau Beach," Delmar, New York, 1987.
11. General Sciences Corporation, Graphic Exposure Modeling NUS Corporation System (GEMS) Landover, Maryland, September, 1987.
12. Chemical, physical, and biological properties of compounds present at hazardous waste sites. Final report prepared for the U.S. Environmental Protection Agency, Clement Associates, Inc., September 1985.
13. Federal Emergency Management Agency, Flood Insurance Rate Map, Town of Hempstead, NY, Community Panel No. 3604670051B, 1985.
14. U.S. Department of Agriculture, Soil Conservation Service, Prime Farmland of New York, August 1979.
15. Letter from Joseph M. Spadafina, President, Autotronic Products, to Mr. Schaefer, Nassau County Department of Health, June 24, 1987.

BIBLIOGRAPHY OF INFORMATION SOURCES (Cont'd)

16. Project Note: W. Schnitzerling, NUS Corp., to Autotronic Products File, Subject: Groundwater usage near site, September 4, 1987.
17. Telecon Note: Conversation between Don Myott, Nassau County Health Department, Pure Waters Division, and S. Shulfer, NUS Corp., May 10, 1988.
18. Atlantic Coast Ecological Inventory, New York, NY-Conn-NJ, U.S. Fish and Wildlife Service, 1980.
19. NYSDEC Memorandum: From Rocky J. Piaggione to Al Machlin (both of NYSDEC), Subject: Autotronics, Inc., May 23, 1983.
20. Chemical/Solvent Waste Report for Autotronic Products, Shipped by Chemical Pollution, June 7, 1985.
21. Chemical/Solvent Waste Report for Autotronic Products, Shipped by Pride Solvents, November 26, 1984.
22. Chemical/Solvent Waste Report, Bureau of Land Resources Management, Nassau County Health Department Permit Number 295.
23. Nassau County Department of Health, Solid Waste Management Facility Permit, Permit Nos. 109, February 6, 1984, and 295, February 7, 1985.
24. Soren, Julian. Results of subsurface exploration in the mid-island area of Western Suffolk County, Long Island, New York. Long Island Water Resources, Bulletin No. 1, 1971.

SECTION 6

BACKGROUND INFORMATION

REFERENCE NO. 1

EPA

Potential Hazardous Waste Site

Preliminary Assessment

PA I
New Site Discovery

FILE COPY

COMPLETED

FILE COPY



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION

01 STATE: 02 SITE NUMBER
NY New

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site)

Autotronic Products

02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER

3300 Lawson Boulevard

03 CITY

Oceanside (Town of Hempstead)

04 STATE

05 ZIP CODE

06 COUNTY

07 COUNTY CODE

08 CONG DIST

NY

11572

Nassau

09 COORDINATES

LATITUDE

LONGITUDE

40° 37' 46."

73° 39' 13."

10 DIRECTIONS TO SITE (Starting from nearest public road)

Site is located on the west side of Lawson Boulevard. Just north of the intersection of Lawson Boulevard and Waukena Boulevard.

III. RESPONSIBLE PARTIES

01 OWNER (if known)

Mr. Joseph M. Spadafina

02 STREET (Business, home, residential)

3300 Lawson Boulevard

03 CITY

Oceanside

04 STATE

05 ZIP CODE

06 TELEPHONE NUMBER

NY

11572

(516) 536-6765

07 OPERATOR (if known and different from owner)

Same as above

08 STREET (Business, home, residential)

09 CITY

10 STATE

11 ZIP CODE

12 TELEPHONE NUMBER

13 TYPE OF OWNERSHIP (Check one)

☒ A. PRIVATE ☐ B. FEDERAL

(Agency name)

☐ C. STATE

☐ D. COUNTY

☐ E. MUNICIPAL

☐ F. OTHER:

(Specify)

☐ G. UNKNOWN

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply)

☐ A. RCRA 3001 DATE RECEIVED:

MONTH DAY YEAR

☐ B. UNCONTROLLED WASTE SITE (CERCLA 103) DATE RECEIVED:

MONTH DAY YEAR

☐ C. NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION

☒ YES

DATE 1/20/86
MONTH DAY YEAR

☐ NO

BY (Check all that apply)

☐ A. EPA

☐ B. EPA CONTRACTOR

☐ C. STATE

☒ D. OTHER CONTRACTOR

☐ E. LOCAL HEALTH OFFICIAL ☐ F. OTHER:

CONTRACTOR NAME(S): EA Science and Technology (Specify)

02 SITE STATUS (Check one)

☒ A. ACTIVE

☐ B. INACTIVE

☐ C. UNKNOWN

03 YEARS OF OPERATION

1981

early 1982

☐ UNKNOWN

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED

Onsite waste disposal of 1,1,1-trichloroethane occurred during 1981 and early 1982. Mr. Spadafina estimates that less than 50 gallons of TCE were dumped onto the paved blacktop surface behind the building during the period of time that dumping occurred.

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION

Soil contamination possible, which may warrant removal of soil. Possible ground-water contamination.

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Impacts)

☐ A. HIGH

(Inspection required promptly)

☒ B. MEDIUM

(Inspection required)

☐ C. LOW

(Inspect on time available basis)

☐ D. NONE

(No further action needed, complete current disposition form)

VI. INFORMATION AVAILABLE FROM

01 CONTACT

Rebecca Ligotino

02 OF (Agency, Organization)

EA Science and Technology

03 TELEPHONE NUMBER

(914) 692-6706

04 PERSON RESPONSIBLE FOR ASSESSMENT

Stephen Barry

05 AGENCY

06 ORGANIZATION

07 TELEPHONE NUMBER

08 DATE

(914) 692-6706

3 24 86
MONTH DAY YEAR



☐ I HIGHLY VOLATILE
☐ J EXPLOSIVE
☐ K REACTIVE
☐ L INCOMPATIBLE
☐ M NOT APPLICABLE

EPA FORM 2070-12 (7-81)



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
NE NW

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ L DAMAGE TO FLOOR 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

None known.

01 ☐ K DAMAGE TO FAUNA 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

None known.

01 ☐ L CONTAMINATION OF FOOD CHAIN 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

None known.

01 ☒ M UNSTABLE CONTAINMENT OF WASTES 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
(Some Punctured Containers Observed Leaking Solvent)
03 POPULATION POTENTIALLY AFFECTED 1000000 04 NARRATIVE DESCRIPTION

Between 1981 and early 1982, an estimated 50 gallons of waste solvent was dumped on paved blacktop behind the facility.

01 ☐ N DAMAGE TO OFFSITE PROPERTY 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

None known.

01 ☐ O CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

The site slopes in the direction of the railroad tracks on the western boundary. Surface runoff would percolate through the soil or evaporate before any contamination would reach sewers or storm drains.

01 ☐ P ILLEGAL/UNAUTHORIZED DUMPING 02 ☐ OBSERVED DATE _____ ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

Between 1981 and early 1982 an estimated 50 gallons of 1,1,1-trichloroethane were illegally dumped on a paved blacktop surface behind the facility.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL OR ALLEGED HAZARDS

None known.

III. TOTAL POPULATION POTENTIALLY AFFECTED: 250,000

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references e.g., State files, Sample analyses, Reports)

References 7 and 8.
E. Site Inspection.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

IDENTIFICATION
SITE NO. _____
DATE _____

1. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ GROUNDWATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED DATE _____
04 NARRATIVE DESCRIPTION _____

☐ POTENTIAL ☐ ALLEGED

Found while in the vicinity of concern was a 100% failure of the site in the source of water for the Long Island Water Company in 1966 and the Village of Rockville Center.

01 ☐ SURFACE WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED DATE _____
04 NARRATIVE DESCRIPTION _____

☐ POTENTIAL ☐ ALLEGED

There is very little surface water in the Rockville Center, Ind. area. Surface runoff would appear to exit the site on the western boundary and permeate through the railroad bedding adjacent to the site. Therefore there is no potential for surface water contamination.

01 ☐ CONTAMINATION OF AIR
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED DATE _____
04 NARRATIVE DESCRIPTION _____

☐ POTENTIAL ☐ ALLEGED

None known.

01 ☐ FREE RELEASE CONDITIONS
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED DATE _____
04 NARRATIVE DESCRIPTION _____

☐ POTENTIAL ☐ ALLEGED

None known.

01 ☐ DIRECT CONTACT
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED DATE _____
04 NARRATIVE DESCRIPTION _____

☐ POTENTIAL ☐ ALLEGED

None reported.

01 ☐ CONTAMINATION OF SOIL
03 AREA POTENTIALLY AFFECTED _____

02 ☐ OBSERVED DATE _____
04 NARRATIVE DESCRIPTION _____

☐ POTENTIAL ☐ ALLEGED

The entire Autozone Products property is paved. The only soil potentially contaminated is the railroad bedding. This soil, adjacent to the property had standing water on it during EA's site inspection 20 January 1966.

01 ☐ DRINKING WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED DATE _____
04 NARRATIVE DESCRIPTION _____

☐ POTENTIAL ☐ ALLEGED

Limited to population served by ground water in the aquifer of concern within a 3-mile radius of the site.

01 ☐ WORKER EXPOSURE/INJURY
03 WORKERS POTENTIALLY AFFECTED _____

02 ☐ OBSERVED DATE _____
04 NARRATIVE DESCRIPTION _____

☐ POTENTIAL ☐ ALLEGED


None known.

01 ☐ POPULATION EXPOSURE/INJURY
03 POPULATION POTENTIALLY AFFECTED _____

02 ☐ OBSERVED DATE _____
04 NARRATIVE DESCRIPTION _____

☐ POTENTIAL ☐ ALLEGED

None known.



Note: Base map enlarged from
SCDOP Spring 1980
Air Photo No. E612,
N4496.

Figure 1-2. Sketch, Autotronic Products, 20 January 1986.

1. EXECUTIVE SUMMARY

Autotronics Products

The Autotronics Products site (New York L.I. No. 180000, EIA L.I. No. New) is an industrial site located at 3300 Lawson Boulevard just north of the intersection of Lawson Boulevard and Waukena Boulevard in Oceanside (Town of Hempstead), Nassau County, New York. Autotronic Products, Inc., owned and operated by Mr. Joseph E. Spadafina, is a business involved in the assembly of printed circuit boards. Mr. Spadafina purchased the operation in June 1982 from Union Corporation of Verona, Pennsylvania (the parent company of the firm Autotronic, Inc. which had been conducting business at 3300 Lawson Boulevard since 1975.)

The only reported violation at the site is the dumping of small amounts of 1,1,1-trichloroethane (TCE) on the ground behind the building. When investigated the practice was found to have been discontinued and the waste TCE was being stored in drums for subsequent removal. This onsite dumping of wastes is believed by the current owner to have occurred for an approximate 1-yr period during 1981 and early 1982. This corresponds to the period of time when some of the soldering operations began on site and when current waste handling procedures were implemented. The practice during this time was, on an occasional basis, to dump a small amount (approximately 1 quart) of residual TCE onto the paved blacktop surface behind the facility. Based on the amount of TCE currently used, Mr. Spadafina estimated that less than 50 gal total of solvent

were dumped in this manner. Current procedures involve collecting wastes in 2 drums--one receiving residual TCE and flux removal, and the other receiving wastes such as acetone and paint thinners resulting from paint operations. These wastes are hauled away on an as-needed basis.

The preliminary HRS scores for this site are as follows: Migration Score (S_M) = 19.82; Direct Contact Score (S_{DC}) = 0. With a confirmed release of contaminants to the ground water, the maximum obtainable S_M is 21.23. There is no overland migration route to surface water for contaminants at the site. The existing data are inadequate to complete a final HRS score. Ground-water quality data are lacking.

In order to prepare a final HRS score, a Phase II study will be necessary to obtain samples of ground water for analysis. The proposed Phase II investigation will include geophysical studies (as possible), the installation of three test borings/monitoring wells, and the collection and analysis of ground-water samples. The estimated cost of the proposed Phase II study is \$41,980.

The Phase I investigation of the Autotronics Products site involved a site

INSTRUMENTAL IN SCIENCE AND TECHNOLOGY, AS WELL AS POLITICAL ECONOMY AND

interviews. The following agencies or individuals were contacted:

Conclusions

Information Received

Mr. Joseph M. Spadafina, Pres.
Autronic Products, Inc.
3300 Lawson Boulevard
Oceanside, New York 11572
(516) 335-6755

Site interview

Mr. Joseph Schacter/Mr. Earl Vetter
Nassau County Department of Health
220 Old Country Road
Mineola, New York 11501
(516) 466-2200

See file number:

Mr. Anthony Cardella, P.E.
Senior Sanitary Engineer
New York State Department of
Environmental Conservation
Division of Solid Waste
SUNY Campus - Building 40
Brooklyn, New York 11794
(516) 781-7901

No file/information.

Mr. Frank Eys
Chief Plant Operator
Department of Water
1 West Chester
Long Beach City, New York 11561
(516) 401-1001

Public water supply and distribution

Mr. Whiston, Superintendent
Rockville Centre Water District
142 Maple Avenue
Rockville Centre, New York 11750
(516) 766-0300

Public water supply and
distribution

REFERENCE NO. 2

NUS CORPORATION

II

0133

AUTOTRONIC PRODUCTS
 Oceanside, New York
 TDD# 02-8708-02
 Project Manager: W. Schnitzerling
 Logbook# 0133
 August 19, 1987

C-38-2-9-123 GUIDANCE FOR PROPER USE OF LOG BOOKS

Purpose

- Types to document onsite activities and be understandable to an outside reader.
- Provides the basis for later written reports.
- Used as an evidentiary document and may be used in legal proceedings.

Distribution

- Controlled by the project manager and distributed as appropriate to personnel designated by the project manager.

General Procedures

- Record information in language which is objective and factual.
- Use ink. Water-proof ink is recommended.
- Leave first two pages blank. They serve as space for the table of contents to be added when the log book is complete.
- The first written page identifies the date, time, TDD number, site name, location, MHS personnel and their responsibilities, other non-MHS personnel and observed weather conditions.
- Start on a new page at the start of each day's field activities. This page should identify date, time, TDD number, site name and location, MHS personnel and their responsibilities, other non-MHS personnel and observed weather conditions.
- List all persons leaving or entering the site.
- Information reported in the log book should be in chronological order.
- Sign and date each page. Log all entries using a 24 hour clock. Entries should be time logged every 15 to 30 minutes.
- Corrections are to be lined through and initialed. No erasures are to be made (highlight).
- Include a sketch or map of the site which can be used to locate photo or sample locations. Note landmarks, indicate north, and if possible include an approximate scale. Include as many sketches and maps as necessary.

- A person not present when field activities were being documented should read each completed page, and comment on and date when satisfied that the written notes are understandable.

Specific Field Activities To Be Documented

- Record the who, what and where of field activities.
- Indicate sampling and photo locations on a site sketch or map.
- As part of the chain of custody procedures, record location sampling information must include sample number, date, time, sampling personnel, sample type, designation of sample as a grab or composite, and any preservative used.
- Information for in-situ measurements must include a sample ID number, the date, time, and personnel taking measurements. Personnel location measurements include but are not limited to pH, temperature, conductivity, flow measurements, continuous air monitoring measurements, and radio gas analysis. If in-situ calculations are necessary they must be checked and signed by a second team member.
- Create a photo log to document photos taken in the field. These must include date, time, photographer, sample number, roll number, frame number, photo ID number and description. Indicate if the film is for slides or prints in the column for roll number. Photo ID numbers can be added at the time the photo log is assembled.
- Record onsite health and safety measures used. Describe observed potential hazards to health and safety. Document the level of protection used, decontamination procedure used and specific decontamination actions.
- When sampling is complete, a summary log is to be completed. It must include date, time, sample number, description, field book reference page, and the number and date of the chain of custody form on which the sample is lined. Indicate whether or not the sample was split.
- Record details regarding relevant information obtained during onsite interviews. Include names of persons interviewed, the interest group represented, their address and phone number.
- Record any other relevant information which would be difficult to generate at a later date.

Table of Contents
Autotronic Products
09/03/87


- 03-5705-03
- NYW 3.22

<u>Description</u>	<u>Page</u>
meeting about site + possible hazards	4-5
Arrival at site, Site Inspection, Description of surrounding area	5-12
Interview with Doris Knight, Nassau County Health Dept. Fire Warden Division	13

9/10/87 The camera's malfunctioned
at the site, no pictures
turned out

William J. Taylor
Beth Cooper 9/7/87

9/3/87



SITE MAP
AUTOTRONIC PRODUCTS, OCEANSIDE, N.Y.
 (NOT TO SCALE)



Autotronic Products
 produces small
 electronic parts for
 The US Government.
 This facility is closely
 monitored by the
 Nassau County Health
 Department and the
 New York State Department
 of Environmental
 Conservation

W. C. Or 09/07/87
Beth Dorsey 9-7-87

TOD # 02 8708-07

09/08/87

Weather AT SITE

Sunny 75°

Wind 15 mph

N.H.

Autotronic Products
Oceanside NY
Nassau County

0615 Arrive at NUS, Edison N.J.

met Brian Pedersen

John Ducar

began to load trucks, sign out (and check)
air monitoring equipment, sign out cameras
and film, and check for change tubes.

0645 Leave NUS with equipment
(did not bring tubes)

0715 Traffic in Staten Island

0750 Accident on the Narrows Bridge

0820 Sunrise Highway backed
up due to construction

0910 Arrive on site

0915 Nus personnel on site

Brian Pedersen SSU

John Ducar 1 PM

W. Schnitzerling PM

DVA and AUSA are started

W. Schnitzerling

09/08/87

Beth Corpey 9-7-87

0917

Site Safety Meeting

attended by

Brian Pedersen

John Ducar

W. Schnitzler

Brian Pedersen

John Ducar

W. Schnitzler

Discussed the possible hazards on this site (TCE or TCM) and discussed the physical hazards (scrapped metal seen on side of building).

0925

NVS Personnel will do a recon of back yard with latex booties, surgical gloves and escape packs, as outlined in the safety plan. Any hits will result in NVS personnel vacating the property and putting on SCBA units.

0930

met Mr Spadafina site contact

Equipment Serial Numbers

OVA 307137 (F)

HNU 469748 (L)

SCBA Escape Pack - 192379 - J Ducar

SCBA Escape Pack 192385 - B Pedersen

SCBA Escape Pack 192094 - W Schnitzler

Mini Rad 469786

- HNU and OVA functioning properly

0935

Mr Spadafina states that


1,1,1, Trichloroethane was used by Autofronics (Not TCE)

W. Schnitzler

0910157

Beth Torrey

9-7-87



Uncertainty 09/03/87

Beth Toupey 9-7-87

0940 ^{US} Mr Spadafino brought us into the back of the property and showed us where the ~~ICA~~ was dumped

0940 OVA reading 5^{ppm} in building (warehouse)
OVA " ~~11~~ 5 outside by door
(readings taken while walking through the warehouse)
OVA reading Right of door 5 ppm
OVA reading 0 outside near fence
HNU No readings

0943 Mr Spadafino leaves to take care of other ~~business~~ business

0945 OVA NO detection from outside
OVA detection of 5ppm inside building (again, to recheck earlier reading)
HNU NO Readings

0950 - NO Readings from HNU or OVA from the down pipes from the roof of building

0952 Description of Site
The ~~site~~ site where the dumping took place is a small area ~~11' x 12'~~ wide x 120' length
The back paved area is common to all the tenants, there is a very slight slope to the left (which is west)

10 00 picture 1 facing North from South boundary of property


W. R. ~~Antony~~ 09/03/87

Beth Torrey 9-7-87

1000 No readings off puddle (small) in back
off property (using HNU + OVA)

10:08 Picture 2 Facing North of weeded
area of site
(No Reading on HNU or OVA)

Picture 3 Facing South - looking at
site

1003 Picture 4  looking at waste
drum of Trichloroethane (properly sealed)
Pictures 5-8 of paved area in back of site

1005 No reading HNU /OVA

1010 No readings ~~HNU~~ HNU /OVA

The back of this property is
a narrow pavement. There
are black stains in the fence line.
In the northern section of this strip
~~there~~ there are weeds and poison ivy.
These weeds also ~~extend~~ extend on the fence line.
In the weeds (in the north section
of the back yard) there are metal scrap
and rusted equipment all thru the area.
Brian got no hits from this area, on either
the HNU or OVA.

The property outside the fence is
RR property owned by the
Long Island RR. The rock gravel fill
is ~~not~~ rusted colored (from the rusted
RR tracks).

W. A. Steiner 09/03/87


Beth Torrey 9-7-87

9
1015 NO Reading from HNU or OVA
The soil across the fence and
near the rock gravel is black stained
This stain extends to from the southern
boundary of Autotronics to the Auto Shop
The Auto shop has several junked cars,
auto parts and wood dumped
on the pavement behind the building.

1020 The area behind the northern
section of the backyard is
also stained black.
The backyard is upgradient from this
stained soil, so are the RR tracks
runoff could occur from either source (the
tracks or the Autotronic Products)

1025 Inside Autotronics

The TCA is stored on a pallet, in a closed drum
near the back door. This door is
constantly locked. There is 1 drum (#277-9C) of TCA
Mr Spadafino says it is over a year old



W. D. Jenkins 02/03/87

Beth Torrey 9-7-87

10.25

Picture of warehouse

10.30

Site history

Mr Spadafina said this building was built in sections the first section was erected in 1951. The owner of the property at that time ~~was~~^{is} is unknown.

The Union Corp bought the building in 1965, Mr Spadafina bought ~~it~~^{the} the building/operation from Union Corp.

As far as Mr Spadafina knows this building was always used to manufacture small electrical components.

- NO Readings ON HAU or OVA

Mr Spadafina estimates 50 gallons of TCA were dumped during 1981-1982. An employee would take the waste TCA and throw it out the back of the ^{warehouse} property.

Currently - the use of TCA is limited because of business slow down and change of production process.

Mr Spadafina said there Autotronics has not purchased new TCA in over a year and there is still 12 drums of

W. J. Spadafina 09/03/87

TCA left from the last purchase. Because of this Autotronics has not disposed of any TCA in over 1 year.

- The TCA is used to scrub off flux from printed circuit boards.
- all workers have access to the Hazardous Waste ~~new storage~~ ^{storage} area because it is ~~(in the open)~~ ^(in the open) in the warehouse.

1035 Mr Spadafino - told me the TCA was dumped in approximately 1 qt batches (these are cleaners & circuit board & at a time). The practice ~~was~~ ^{is} (of dumping waste) was exposed when the employee who dumped it was laid off. He reported the incidents to The EPA. Mr Spadafino was fined \$1000.00 for these dumpings. (Eventually the employee was fired for unrelated reasons).

1040 NO readings on DNA, HNU, or min. rad. Area is 1200 sq ft. Spill containment is a small step to get out door.
- Picture 10.11 - the back of the property.
- The hazardous chemicals are ~~not~~ ^{not} stored next to the waste drum. Currently there are NO hazardous chemicals on this site.

W. J. Spadafino 09/03/87

Beth Dorsey 9-7-87

1050 20 people (On the average work at Autotronics)
- There are no chemicals (hazardous or not)

1100 - packing truck to leave site
- Samples were not taken during this SE

1115 leave site, will drive to surface water to investigate possible contamination routes

1145 Found landfill pit at the end of Lawson Rd. Ave. surface water running towards Autotronics is appears very dirty

1215 heading to Nassau County Health Department to speak to Don Myott

130 Arrive at NCID

210 Leave NCID after speaking to Don Myott - of Nassau Bureau of Public Water
(NCID = Nassau County Health Department)

- Mr. Myott works in the NCID - Public works Division

- People in this area use surface water for recreation (swimming, boating and fishing within 3 miles of this site). There are no drinking water intakes from surface water in this area

W. R. T. L. H. 09/03/87

Beth Torrey 9-7-87

9/05/87 - followup of interview
with D. M. H.

He stated the closest
Drinking Water well was 2.5
miles from the site, (he had
estimated this figure) He
was wrong, the closest ~~well~~ drinking water
well is 1.5 miles from the site.
This well serves Rockville Centre
Village, and the latest population
estimates for this village are ^{is} 29,000. (The old estimate is 25,000,
from the NY Atts of Community
Water Systems).

Beth Storphey 9-7-87

09/03/87
W. Schipke

REFERENCE NO. 3

**LONG ISLAND WATER RESOURCES
BULLETIN 12**

**HYDROGEOLOGY OF THE TOWN OF NORTH HEMPSTEAD,
NASSAU COUNTY, LONG ISLAND, NEW YORK**



**Prepared by the
U.S. GEOLOGICAL SURVEY**

**in cooperation with the
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS**

**Published by
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS**

1979

The correlation of stratigraphic units of Pleistocene and Cretaceous on Long Island involves the correlation of (a) Pleistocene deposits referred to as the Gardiners Clay and Jameco Gravel, and (b) Cretaceous deposits, with deposits of similar age in New Jersey. For example, recent studies by Sirk (1974) have indicated that deposits included in the Raritan Formation on Long Island may be equivalent in part to those included in the Magothy Formation in New Jersey. Because hydrogeologic units do not need to be equivalent to stratigraphic units, questions as to stratigraphy and correlation of these deposits are not discussed further in this report. Additional information on this subject is given in the reports mentioned in the section "Previous Investigations."

The division of the sedimentary sequence into separate hydrogeologic units that together form the ground-water reservoir underlying the Town of North Hempstead is essentially the same in this report as in works by Swarzenski (1963) and Isbister (1966). Many of the correlations of well-drillers' logs used in this study are the same as those made by Swarzenski (1963) and Isbister (1966); therefore, this report could in some respects be considered an updating of these earlier studies.

Swarzenski (1963, p. 32) considered the Lloyd Sand Member of the Raritan Formation (Lloyd aquifer) and the Jameco Gravel (Port Washington aquifer) to be hydrologically connected and to form what was at that time called the deep confined aquifer (tables 2 and 3). He regarded the lower limit of the aquifer as the bedrock surface and the upper limit as the clay member of the Raritan Formation (Raritan clay) and the Gardiners Clay (Port Washington confining unit). The premise that the two units are hydrologically connected is not questioned in this report. (See pl. 3, sections C-C' and D-D', and pl. 4, section E-E'.)

The Port Washington and Lloyd aquifers and the Port Washington confining unit and Raritan clay are treated as four distinct hydrogeologic units in this report because (1) this approach will facilitate future studies of the hydrology of each unit as a whole, and (2) the individual units may have different hydraulic characteristics as a result of their separate origin. The reasons why new hydrogeologic names have been proposed in this report for the Jameco Gravel and Gardiners Clay of Swarzenski (1963) are given in the sections "Port Washington aquifer" and "Port Washington confining unit."

Hydrogeologic Units

BEDROCK

Bedrock of Lower Paleozoic and (or) Precambrian age underlies all of western Long Island (Fisher and others, 1962). The bedrock generally consists of schist and gneiss and contains many igneous intrusions; its upper part is deeply altered by weathering (Perlmutter, 1949, p. 13). The zone of decay commonly consists of red, gray, yellow, white, green, or mottled colored clay, or sandy clay with partly decayed rock and mineral fragments

(Perlmutter, 1949, p. 13). If good core samples are available, a definite downward gradation from an almost pure clay to "sound" rock can be observed. Decayed bedrock samples are characterized by angular and ragged crystals of quartz, garnet, biotite, amphibole, feldspar, and their altered equivalents. The weathered zone ranges from 0 to more than 67 feet in thickness and may be locally absent as a result of erosion.

Eighteen of the 34 wells that have been drilled into bedrock in the Town of North Hempstead probably penetrated weathered bedrock. Most drillers' logs describe the bedrock as being composed of blue, brown, gray, or multicolored clay, sandy clay, or sand and clay. The clay is usually described as being "tough" and occasionally containing stones or boulders. Without indicative cores or rock samples, weathered bedrock cannot be reliably distinguished, nor can the precise top of the weathered bedrock zone be determined.

The altitude and configuration of the bedrock surface in the Town of North Hempstead are shown in figure 2. The bedrock surface dips 62 ft/mi southeastward and ranges from 166 feet below sea level along the north shore to more than 900 feet below sea level in the southeast part of the Town of North Hempstead. The configuration of most of the bedrock surface may be attributed to fluvial erosion before Late Cretaceous time; the configuration of the bedrock surface in the north half of Great Neck and Manhasset Neck may have been locally affected by glacial and fluvial erosion during Pleistocene time. Available well data are sufficient to define only the general structural trend of the bedrock surface in the North Hempstead area.

Bedrock is generally regarded as the base of the ground-water reservoir on Long Island because of its density and low permeability. No wells in the Town of North Hempstead are known to obtain water from bedrock; it is possible, however, that joints and fractures in the bedrock could provide yields sufficient for some domestic supplies.

LLOYD AQUIFER

The Lloyd aquifer is the equivalent of the Lloyd Sand Member of the Raritan Formation of Late Cretaceous age (Cohen and others, 1968, p. 18). The Lloyd deposits overlie bedrock and are overlain by the Raritan clay. The inferred extent, altitude, and configuration of the top of the Lloyd aquifer in the Town of North Hempstead are shown in figure 3. The lithologic composition, as indicated by drillers' logs and lateral relationships of the aquifer, are shown on plates 2 to 4, the locations of the sections are shown on plate 1 and in figure 3.

The Lloyd aquifer consists of discontinuous layers of gravel, sand, sandy clay, silt, and clay. As determined from the best available samples, the sand and gravel beds are composed of yellow, white, and gray quartz and contain minor amounts of chert and other stable minerals. The quartz grains are angular to subrounded, and the beds contain varying amounts of interstitial clay. White, gray, and buff silt and clay lenses are common. Thin lenses and scattered particles of lignite also occur.

Drillers usually describe the Lloyd sediments in the Town of North Hempstead as consisting of white and, occasionally, light-gray to dark-brown coarse sand and gravel or grit, with some interbedded fine to medium sand and clay. The clay is usually described as brown or gray but may occasionally be described as white, pink, red, or multicolored.

The Lloyd aquifer, as inferred from available data, may locally consist of either a unit composed largely of sand and gravel, as shown on the log of well N 24 (pl. 2, section B-B') or as a unit that consists of a lower sand and gravel sequence and a finer grained sequence above. The two units are separated by a thin, clayey zone, as shown on the log of well N 8477 (pl. 4, section E-E'). The clay zone generally consists of from one to three clay beds that cannot be correlated reliably over any great distance.

Drillers' logs indicate that the upper, finer grained sequence commonly consists of beds of sandy clay and fine to medium sand that generally contain thin beds of clay. Elsewhere, the logs indicate that the upper part may consist of gravelly clay, as shown on the log of well N 1958 (pl. 3, section D-D') or sand and gravel.

By the end of 1975, 20 wells had penetrated the full thickness of the Lloyd aquifer. The average thickness of the aquifer, as determined from drillers' logs, is 132 ft but ranges in thickness from 0 to more than 200 ft (fig. 4).

The top of the Lloyd aquifer decreases in altitude southeastward from 155 ft below sea level in the Great Neck area to more than 650 ft below sea level in the southeast corner of the Town. (See fig. 3.)

The Lloyd is a major aquifer in the Town of North Hempstead and is the source of water for 15 public-supply wells. The aquifer is probably hydraulically continuous with the adjacent Port Washington aquifer and the upper glacial aquifer in the Great Neck and Manhasset Neck areas. Water in the Lloyd aquifer is confined under artesian pressure beneath the Raritan clay.

Well yields during test pumping of large-capacity public-supply wells screened in the Lloyd aquifer have ranged from 510 gal/min to as much as 1,600 gal/min. The specific capacities of these wells range from 6 to 31 gal/min per foot of drawdown.

EXPLANATION

— BEDROCK CONTOUR—Shows approximate altitude of bedrock surface.
--- Contour interval 50 feet. Datum

RARITAN CLAY

The Raritan clay is a distinct hydrogeologic unit that extends throughout much of the Town of North Hempstead (fig. 5). In this area the Raritan clay may be equivalent to the unnamed clay member of the Raritan Formation of Late Cretaceous age. The clay overlies the Lloyd aquifer and is in turn overlain by the Magothy aquifer. The composition and relationship of the Raritan clay to other hydrogeologic units is shown in tables 2 and 3 and plates 2 to 4.

The thickness of the clay, as determined from drillers' logs, ranges from 20 ft to 195 ft; within the Town of North Hempstead it is inferred to range from 0 to about 200 ft (fig. 6).

The Raritan clay consists mainly of clay and varying amounts of silt and sand. It is variously described as light to dark gray with beds of red, white, yellow, or mottled clay. Drillers have also noted sandy zones within the upper part of the clay. Core samples show that the clay may be laminated and may contain pyrite and lenses of lignite.

The Raritan clay is a significant hydrogeologic unit because it confines water in the underlying Lloyd aquifer. Although its hydraulic conductivity is very low, it does not entirely prevent movement of water between the Magothy and Lloyd aquifers. Some public-supply wells and other wells obtain part of their water supply from the sandy zones in the upper part of the Raritan clay.

MAGOTHY AQUIFER

The Magothy aquifer is composed of Upper Cretaceous sediments that overlies the Raritan clay. It is in turn overlain by deposits of Pleistocene age that form the upper glacial aquifer (pls. 2-4 and tables 2, 3).

The Magothy aquifer consists mainly of lenticular and discontinuous beds of very fine to medium sand, commonly clayey or containing thin clay lenses, that are interbedded with clay and sandy clay, silt, and some sand and gravel. Beds of coarse sand and gravel commonly occur in the lower 100 to 150 ft of the aquifer. This coarser zone may have been referred to in some reports as "basal Magothy." The sediments in the aquifer seem to grade upward from coarser grained at the base to finer grained at the top. The greater proportion of the clay and sandy clay occurs in the upper half of the aquifer. Thick beds of clay occur locally at the top of the aquifer (see pl. 4, section E-E', well N 4327) and seem to be distributed irregularly throughout the area.

Most of the original Cretaceous deposits in the Long Island Sound area were extensively eroded or removed before early(?) Pleistocene time. The northern limit of these deposits and of the Magothy aquifer is an erosional scarp, or ridge, into which later Pleistocene streams cut deep, north-trending valleys. These valleys were modified further by still later glacial action and are now buried beneath deposits of Pleistocene age (pls. 2-4 and fig. 7). The erosion in many of these valleys was sufficient to cut through the

Magothy aquifer into the underlying Raritan clay. The upper surface of the Magothy in the area not cut by valleys ranges in altitude from slightly below sea level to more than 200 ft above sea level (fig. 7).

The inferred extent, altitude, and configuration of the top of the Magothy aquifer in the Town of North Hempstead are shown in figure 7. The continuity, composition, and relationships of the aquifer to adjacent hydrogeologic units are shown in plates 2 to 4 and tables 2 and 3. The aquifer ranges in thickness from 0 to more than 500 ft (fig. 8); its maximum known thickness in the Town of North Hempstead is 530 ft at well N 2602 in the southeast corner of the Town (pl. 1).

It is quite possible that the uppermost part of the Magothy contains deposits of Pleistocene age or, conversely, that the lower part of the upper glacial aquifer contains Cretaceous deposits because the boundary between the Cretaceous and Pleistocene deposits in some areas is indistinguishable. In the area north of the glacial outwash plain (pl. 1), it is often difficult to differentiate between the upper glacial aquifer and the upper part of the Magothy aquifer from drillers' logs because Pleistocene deposits rest upon Cretaceous sediments of similar composition and show no significant lithologic differences that drillers would be likely to note. Also, many drillers' logs of wells north of Northern Boulevard are old and seem to be generalized; determination of the contact between the units from these logs is therefore of doubtful reliability. Some sample logs that were used in this study were prepared from cuttings collected from the mud ditch and are probably contaminated by recirculated materials. Thus, precise determination of the depth of the contacts from these samples is also uncertain.

The Magothy aquifer is the principal aquifer underlying Long Island and is the island's main source of water for public supplies. The sandbeds within the aquifer are moderately to highly permeable. The reported yield during test pumping of 90 large-capacity wells screened in the Magothy aquifer in the Town of North Hempstead ranged from 300 gal/min to as much as 1,543 gal/min. The average yield of the 90 wells was 1,000 gal/min, and specific capacities ranged from 7 to 77 gal/min per foot of drawdown, with an average specific capacity of 29.6 (gal/min)/ft. Wells screened in the basal part of the aquifer may yield up to 1,400 gal/min.

The large amount of clay in the upper half of the aquifer causes the water to become increasingly confined with depth. Along the north shore, the Magothy aquifer is probably in hydraulic continuity with the adjacent Port Washington aquifer. The Magothy also has a generally high degree of hydraulic continuity with the overlying upper glacial aquifer, but the degree of continuity may vary considerably from place to place.

The upper part of the Magothy aquifer is locally unsaturated in the Town of North Hempstead. The location and approximate thickness of the unsaturated zone within the aquifer in June 1976 is shown in figure 9. The maximum thickness of the unsaturated zone during this period is estimated to have been 80 ft. Where the Magothy is unsaturated, the upper surface of the saturated zone is the water table; elsewhere the Magothy is saturated and the water table is in the overlying upper glacial aquifer.

The interpretation and correlation of the Port Washington confining unit and the Port Washington aquifer sequences shown in plate 4, section E-E' on the log of well N 6089, differs from that shown by Swarzenski (1963) in his plate 6. Swarzenski (1963, p. 16) considered the sequence shown as the Port Washington confining unit on the log of well N 6089 (plate 4, section E-E') in this report to be part of a silt and clayey sand facies within the clay member of the Raritan Formation. The correlation has been revised in this report because (1) a distinct lithologic change occurs just north of and along the inferred area of the Pleistocene-Cretaceous contact between wells N 6095 and N 4223 (pl. 4, section E-E'); (2) the sandy facies runs generally east-west along and parallel to the front of the Cretaceous deposits to the south; and (3) a sandy facies of this extent and thickness has not been found elsewhere within the clay member of the Raritan Formation in the north-shore area of Long Island.

The Port Washington confining unit confines the water in the underlying Port Washington aquifer. Swarzenski (1963, p. 23) considered the deposits that form the unit to be variable enough in thickness and lithology to permit local interchange of water with that of the adjacent aquifers. The sand and gravel deposits within the unit are tapped by some wells.

UPPER GLACIAL AQUIFER

The upper glacial aquifer consists of deposits of late Pleistocene and Holocene age that overlie the Gardiners Clay (de Laguna, 1948, p. 16). The upper glacial aquifer overlies the Magothy aquifer and the Port Washington confining unit and locally abuts against or overlies the Port Washington aquifer. The upper surface of the aquifer and these deposits form the present land surface, except where they are overlain by deposits of Holocene age or by landfill. The extent and relationships of these deposits to the adjacent hydrogeologic units are shown on plates 2 to 4.

The upper Pleistocene deposits are locally covered by a thin layer of Holocene deposits along the shore of Long Island Sound and its bays and along some streams, lakes, and upland marshes. The Holocene deposits are too thin to be differentiated in the sections.

The upper Pleistocene deposits consist of beds of fine to coarse stratified sand and gravel, boulder clay or till consisting of unstratified mixtures of clay and boulders, and some freshwater lake deposits composed of silt and clay (Perlmutter, 1949, p. 24).

The upper Pleistocene deposits in the Town of North Hempstead form two hydrologically significant areas--a northern area of moraine and a southern area of glacial outwash. The approximate boundary between the two areas, shown on plate 1, is taken from the surficial geology maps of Swarzenski (1963, pl. 8) and Isbister (1966, pl. 2).

The outwash area is underlain by stratified deposits of sand and gravel that may locally contain thin clay beds. These deposits have a high permeability and allow precipitation to percolate downward with relative ease to the water table and thence into the underlying aquifers.

The morainal area is underlain both at the surface and at depth by beds of till that can support perched water tables or retard the downward movement of water to the water table.

The deposits forming the upper glacial aquifer in the Town of North Hempstead range in thickness from 6 ft to more than 350 ft (fig. 14). This extreme variation is due to the uneven surface upon which the materials were deposited and because the upper surface of the deposits is the present irregular land surface. The deposits in the outwash area range in thickness from 14 ft to about 165 ft.

The upper glacial aquifer, as defined and used by the U.S. Geological Survey on Long Island, includes both the unsaturated and saturated parts of the upper Pleistocene deposits. The estimated saturated thickness of the aquifer in June 1976 is shown in figure 15. The upper surface of the saturated zone is the water table. As can be seen from figure 15, the upper Pleistocene deposits are locally unsaturated; in these areas the water table is in the underlying Magothy aquifer (pls. 2, 3 [section D-D'], 4; figs. 9 and 15).

Buried valleys that cut into the Cretaceous deposits in the sections (pl. 2 [section B-B'], pl. 3 [section D-D'], pl. 4 [section F-F']) and maps (figs. 3, 5, and 7) have been inferred from correlations of the well-log data and from the geologic history of the north-shore area of Long Island. These valleys may be important hydrologically because of their possible higher permeability, which would facilitate the movement of water between aquifers in response to differing hydrostatic heads within the aquifers. All deeper valleys shown on the figures and maps in this report have been previously mapped by Swarzenski (1963). Isbister (1966, pl. 3) and Jensen and Soren (1974, sheet 1) have reported similar buried valleys that have been cut deeply into or through the Cretaceous deposits.

The buried valley beneath Manhasset Bay, inferred from the driller's log of well N 291 (pl. 3, section C-C'), has been cut to at least 195 ft below sea level. The log shows that "quicksand" and very fine white sand were penetrated from 50 to 237 ft below land surface. This sand is considered to be part of the upper Pleistocene deposits that fill the valley. Sandbeds in similar stratigraphic position have been reported from wells N 23, N 216, and N 314 (pl. 1). The stratigraphic horizon occupied by this sand sequence, as shown in plate 3 (section C-C'), is one that was once probably occupied by clay of the Port Washington confining unit before it was removed by erosion. The valley is assumed to extend to bedrock because the underlying unconsolidated deposits would have been eroded with great ease. However, no data to support this assumption are as yet available.

Swarzenski (1963, pl. 3) postulated that other buried valleys had been cut into the Cretaceous deposits. Some of these were not substantiated during the present study. The buried valley on Swarzenski's plate 3, which extends south from the south end of Manhasset Bay, was apparently based on interpretation and correlation of the log of well N 5710. The recording of this log in the present study with those of nearby wells (pl. 1) suggests that the valley may not exist.

the bottoms of the bays and lakes have not been differentiated from the upper glacial aquifer because they are too thin. These deposits may be hydrologically significant in that they locally retard the downward movement of saltwater from Long Island Sound and its bays into the underlying aquifers. In general, the deposits are not a source of freshwater because they are mostly above the water table or contain brackish or salty water.

SUMMARY

The ground-water reservoir underlying the Town of North Hempstead is composed of unconsolidated local deposits of Holocene age, glacial deposits of Pleistocene age, and coastal-plain deposits of continental and marine origin of Late Cretaceous age. The deposits consist of clay, silt, sand, and gravel. Weathered and crystalline bedrock of Lower Paleozoic and (or) Precambrian age underlies the unconsolidated deposits and forms the virtually impermeable base of the ground-water reservoir.

The Upper Cretaceous deposits in the Town of North Hempstead have been subdivided into three hydrogeologic units, which are, from oldest to youngest, the Lloyd aquifer, the Raritan clay, and the Magothy aquifer. These units are present throughout most of the Town and are recognized as distinct hydrogeologic units (figs. 3, 5, and 7). The deposits dip and thicken to the southeast; their maximum thickness in the Town of North Hempstead is about 950 ft.

The Lloyd aquifer (fig. 3) rests upon bedrock and consists of lenticular deposits of clay, silt, sandy clay, sand, and gravel. The top of the aquifer dips southeast from about 155 ft below sea level in Great Neck to more than 650 ft below sea level in the southeast corner of the Town of North Hempstead. The aquifer ranges from 0 to 205 ft in thickness. The average thickness, as determined from drillers' logs of 20 wells that have penetrated the full thickness of the aquifer, is 132 ft.

The Lloyd aquifer in the Town of North Hempstead is tapped by 15 public-supply wells, mainly in the north and westernmost parts of Town. Water in the aquifer is confined beneath the Raritan clay. In the Great Neck and Manhasset Neck areas, the aquifer is probably hydraulically continuous with adjacent hydrogeologic units of Pleistocene or Late Cretaceous and Pleistocene age.

The Raritan clay (fig. 5) is a significant confining unit that consists mainly of clay and silty clay and some sandy clay and sand in the upper part. The clay has a very low hydraulic conductivity but does not prevent movement of water between the overlying Magothy aquifer and the underlying Lloyd aquifer. The clay ranges from 0 to about 195 ft in thickness.

The Magothy aquifer (fig. 7) is the principal aquifer underlying the Town of North Hempstead. It consists mainly of lenticular beds of very fine to medium sand that are interbedded with beds of clay and sandy clay, silt, and some sand and gravel. Most of the clay is in the upper half of the unit. Beds of coarse sand with gravel are found at most, but not all, locations in the lower 100 to 150 ft of the unit. The aquifer reaches maximum thickness in the southeast corner of the Town, where its thickness is about 530 ft.

The large amount of clayey sediments in the upper half of the Magothy aquifer causes the water to become increasingly confined with depth. The hydrogeologic relationships between the Magothy aquifer and the adjacent aquifers of Pleistocene or Late Cretaceous and Pleistocene age (pl. 2, section B-B' and pls. 3 and 4) suggest that the units may be in close hydraulic continuity. Similarly, a high degree of hydraulic continuity probably exists in many areas between the Magothy and the overlying upper glacial aquifer.

The Cretaceous deposits in the north half of Great Neck and Manhasset Neck have been extensively eroded and probably have been removed from some areas. In their place is a thick sequence of deposits of Pleistocene and Holocene(?) age. These deposits and any remaining deposits of Cretaceous age have been subdivided into three hydrogeologic units, which are, from oldest to youngest, the Port Washington aquifer, the Port Washington confining unit, and the upper glacial aquifer. The Port Washington aquifer and Port Washington confining units, first identified and named in this report, are equivalent to the Jameco Gravel and Gardiners Clay, as mapped by Swarzenski (1963). The terms "Port Washington aquifer" and "Port Washington confining unit" are used in this report in preference to the names Jameco Gravel and Gardiners Clay because the latter imply correlations, which are questionable, with deposits of those names elsewhere on Long Island.

The Port Washington aquifer (fig. 10) consists mainly of sand or sand and gravel and varying amounts of interbedded clay, silt, and sandy clay. The deposits either rest upon bedrock or overlap or abut against the adjacent Cretaceous units (pl. 2, section B-B', and pls. 3 and 4). Locally they occur as valley fill in channels cut into the Cretaceous deposits. The deposits are probably thickest in the central parts of Great Neck and Manhasset Neck, where they average well over 100 ft in thickness. The Port Washington aquifer is a major source of freshwater in the Great Neck and Manhasset Neck areas. Water in the aquifer is confined by the overlying Port Washington confining unit. The hydrogeologic relationships between this aquifer and the Lloyd and upper glacial aquifers suggest that the aquifers are in hydraulic continuity.

The Port Washington confining unit (fig. 12) overlies the Port Washington aquifer and is in turn overlain by deposits that form the upper glacial aquifer. The deposits that form the confining unit locally overlap the adjacent Cretaceous units and constitute part of the upper valley fill in channels cut into the Cretaceous units (pl. 2, section B-B', pl. 3, section D-D', and pl. 4). The deposits consist of clay and silt with scattered lenses of sand or sand and gravel. Their maximum thickness is about 190 ft in Manhasset Neck and 234 ft in Great Neck.

The top of the confining unit in much of Great Neck ranges in altitude from 19 ft above sea level to about 50 ft below sea level, whereas in much of Manhasset Neck, the top of the confining unit is 40 ft to 60 ft lower and ranges from 36 ft to about 100 ft below sea level. The top of the unit on Manhasset Neck, however, is normally 50 ft to 100 ft below sea level.

The upper glacial aquifer consists of deposits of late Pleistocene and Holocene age that overlie the Magothy aquifer and the Port Washington confining unit and that locally abut against or overlie the Port Washington aquifer (pls. 2-4). The top of the upper Pleistocene deposits is the present land surface, except where they are locally overlain by thin deposits of Holocene age.

The upper Pleistocene deposits are composed of beds of fine to coarse stratified sand and gravel, boulder clay, or tills, consisting of unstratified mixtures of clay and boulders, and some freshwater lake deposits of silt and clay (Perlmutter, 1949, p. 24). The deposits in the Town of North Hempstead can be divided into two hydrologically significant areas on the basis of general lithologic composition. The southernmost part of the Town is underlain by highly permeable glacial outwash consisting of stratified sand and gravel and occasional thin clay beds; the rest of the Town is underlain by glacial moraine that consists of sand and gravel, boulder clay, till, and lake deposits.

The deposits forming the upper glacial aquifer range in thickness from 6 ft to more than 350 ft. The extreme variation in thickness results from the highly eroded surface upon which these materials were deposited and the irregularity of their upper surface, which is the present land surface. The outwash deposits range in thickness from 14 ft to about 165 ft. The estimated thickness of the saturated zone in the aquifer during June 1975 ranged from 0 to about 350 ft.

The upper glacial aquifer is the source of all recharge to the underlying aquifers but is also a source of contamination because it receives large amounts of cesspool effluent and surface pollutants, which percolate down to the water table.

The aquifer was tapped in the past by many public-supply wells. However, since it has become polluted it is tapped only sparsely as a public supply. The aquifer is now tapped mainly by domestic, irrigation, commercial and industrial wells.

REFERENCE NO. 4

LONG ISLAND WATER RESOURCES
BULLETIN LIWR-6

ANALOG MODEL PREDICTION OF THE HYDROLOGIC EFFECTS
OF SANITARY SEWERAGE IN SOUTHEAST NASSAU
AND SOUTHWEST SUFFOLK COUNTIES, NEW YORK

By

Grant E. Kimmel, Henry F. H. Ku, Arlen W. Harbaugh,
Dennis J. Sulam, Rufus T. Getzen

U. S. Department of the Interior
Geological Survey

Prepared by the
U. S. GEOLOGICAL SURVEY

in cooperation with the
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS
SUFFOLK COUNTY DEPARTMENT OF ENVIRONMENTAL CONTROL
SUFFOLK COUNTY WATER AUTHORITY

Published by the
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS

1977

Long Island has many streams, most of which are relatively short-- 15 mi (24 km) or less (fig. 2). Approximately 90 percent of the flow in these streams is derived from ground water; the amount of flow depends on the elevation of the water table. When the water table declines, the position of the start of flow in streams can move downstream; also ground-water gradients to the streams are generally reduced. Thus, the effect of a decline in the water table is a decrease in streamflow and stream length. Prior to urban development, about 60 percent of the water infiltrating the aquifer was discharged to streams (Franke and McClymonds, 1972, table II). The dependency of streamflow on altitude of the water table is a significant factor in any model of Long Island's hydrologic system.

Table 1.--Generalized description of hydrogeologic units underlying study area 1/

Hydrogeologic unit	Lithology and water-bearing character
Upper glacial aquifer	Mainly sand and gravel of moderate to high permeability; also includes clayey deposits of till of low permeability.
Gardiners Clay	Clay, silty clay, and a little fine sand of low to very low permeability.
Jameco aquifer	Mainly medium to coarse sand of moderate to high permeability.
Magothy aquifer	Coarse to fine sand of moderate permeability; locally contains gravel of high permeability and abundant silt and clay of low to very low permeability.
Raritan clay	Clay of very low permeability; some silt and fine sand of low permeability.
Lloyd aquifer	Sand and gravel of moderate permeability; some clayey material of low permeability.

1/ Adapted from Cohen, Franke, and Foxworthy (1968).

REFERENCE NO. 5

Uncontrolled Hazardous Waste Site Ranking System

A Users Manual (HW-10)

Originally Published in
the July 16, 1982, *Federal Register*

United States
Environmental Protection
Agency

1984

TABLE 2
PERMEABILITY OF GEOLOGIC MATERIALS*


Type of Material	Approximate Range of Hydraulic Conductivity	Assigned Value
Clay, compact till, shale; unfractured metamorphic and igneous rocks	$<10^{-7}$ cm/sec	0
Silt, loess, silty clays, silty loams, clay loams; less permeable limestone, dolomites, and sandstone; moderately permeable till	$10^{-5} - 10^{-7}$ cm/sec	1
Fine sand and silty sand; sandy loams; loamy sands; moderately permeable limestone, dolomites, and sandstone (no karst); moderately fractured igneous and metamorphic rocks, some coarse till	$10^{-3} - 10^{-5}$ cm/sec	2
Gravel, sand; highly fractured igneous and metamorphic rocks; permeable basalt and lavas; karst limestone and dolomite	$>10^{-3}$ cm/sec	3

*Derived from:

Davis, S. N., Porosity and Permeability of Natural Materials in Flow-Through Porous Media, R.J.M. DeWiest ed., Academic Press, New York, 1969


Freeze, R.A. and J.A. Cherry, Groundwater, Prentice-Hall, Inc., New York, 1979

MEAN ANNUAL LAKE EVAPORATION (In Inches)



Based on period 1946-55

1 YEAR 24-HOUR RAINFALL (inches)



REFERENCE NO. 6

NUS CORPORATION

TELECON NOTE

CONTROL NO: 02-8708-02	DATE: 8/5/87	TIME: 1000
DISTRIBUTION: Autotronic Products		
BETWEEN: Rocky Piaggione	OF: NYDEC Environmental Enforcement ALBANY	PHONE: 1(914) 761-6660
AND: W. Schutzerling		(NUS)
DISCUSSION:		
<p>The possible sampling of Autotronic Products - The past problems at this site.</p> <p>Between 1981 and 1982 approximately 50 gallons of TCE (process water) were dumped in the back of this site by the employees. They were instructed to do it by management. The waste was from a Sorec bath, when it was troubled or dirty to use it was taken and dumped out the back door. It held about 5 gallons. This bath was emptied 10 times before this practice was stopped.</p> <p>The area, in which the dumping occurred is a small (10' x 10') asphalt, common yard. (Autotronics rents a section of a small building. There are other tenants - businesses - in this building. They all share a common back yard). The yard slopes to the back fence. The property is bordered by the Long Island Rail Road tracks. The waste TCE is believed to run off the asphalt under the fence onto the I.R.R.'s property. (Here it is to) Since there are no storm drains in this area it is believed the TCE leached into the soil + into the groundwater.</p> <p>Autotronics was fined \$1,000.00 by the NYDEC. There wasn't any sampling done on this site, and as far as Mr. Piaggione knows there are no other problems at this site. Autotronics now recycles their waste TCE, or it is hauled off site (by approved hauliers), depending on the quality of the particular bath.</p>		

REFERENCE NO. 7

CONTROL NO:

02-8708-02

DATE:

08/05/87

TIME:

1430

DISTRIBUTION:

Autotronic Products

BETWEEN:

Joe Schechter

OF: Nassau County
Division of
Health

PHONE:

1 (516) 535-2406

AND:

WSchnitzerling

(NUS)

DISCUSSION:

Autotronic Products is a small company that manufactures small electronic devices. They were fined by the NYDEC Enforcement Division for illegally dumping TCE in the back of their property. Autotronics shares a common backyard with the other small companies sharing this building. The area where the waste was dumped is asphalt, so the TCE ran off this property onto the ~~the~~ bordering property, owned by the Long Island Rail Road. Since they were fined Autotronics has not had any problems (involving wastes). They now Recycle TCE and what they can't reuse they ~~would~~ have hauled off site by EPA licensed haulers. Approximately 1 drum a year is hauled off site. This site was recently inspected by the Nassau County Division of Health ~~and~~ (March 1987) and no problems or violations were recorded.

Although wastes were dumped at this site (approx 50 gallons over a year period between 1981 & 1982), sampling or any type of remediation were never undertaken. Since the entire property is paved, the wastes were believed to have ~~run off~~ migrated to the LIRR's property, because of the slope of the property. Mr. Schechter said the ~~only subtle noticeable~~ weeds behind Autotronics (and on LIRR property) were bushy except for one denuded spot, but he could not confirm this flora damage was from the dumped TCE.

ACTION ITEMS:

REFERENCE NO. 8



New York State Atlas of Community Water System Sources 1982

NEW YORK STATE DEPARTMENT OF HEALTH
DIVISION OF ENVIRONMENTAL PROTECTION
BUREAU OF PUBLIC WATER SUPPLY PROTECTION

NASSAU COUNTY

ID NO COMMUNITY WATER SYSTEM POPULATION SOURCE

Municipal Community

1	Albertson Water District.	13500.	Wells
2	Bayville Village.	7500.	Wells
3	Bethpage Water District.	32000.	Wells
4	Bowling Green Water District.	12000.	Wells
5	Carle Place Water District.	11000.	Wells
6	Citizens Water Supply Company.	30000.	Wells
7	Deforest Drive Association.	25.	Wells
8	East Meadow Water District.	52000.	Wells
9	Farmingdale Village.	7946.	Wells
10	Franklin Square Water District.	20000.	Wells
11	Freeport Village.	38272.	Wells
12	Garden City Park Water District.	22596.	Wells
13	Garden City Village.	22927.	Wells
14	Glen Cove City.	24618.	Wells
15	Hempstead Village.	40404.	Wells
16	Hicksville Water District.	58000.	Wells
17	Jamaica Water Supply Company.	128448.	Wells
18	Jericho Water District.	64000.	Wells
19	Levittown Water District.	50000.	Wells
20	Lido-Point Lookout Water District.	10000.	Wells
21	Locust Valley Water District.	8500.	Wells
22	Long Beach City.	34073.	Wells
23	Long Island Water Corporation.	258936.	Wells
24	Manhasset-Lakeville Water District.	44730.	Wells
25	Massapequa Water District.	52000.	Wells
26	Mill Neck Estates Water Supply.	240.	Wells
27	Mineola Village.	20600.	Wells
28	New York Water Service.	172180.	Wells
29	Old Westbury Village.	3100.	Wells
30	Oyster Bay Water District.	10225.	Wells
31	Plainview Water District.	40000.	Wells
32	Plandome Village.	2616.	Wells
33	Port Washington Water District.	35000.	Wells
34	Rockville Centre Village.	25405.	Wells
35	Roosevelt Field Water District.	1640.	Wells
36	Roslyn Water District.	27500.	Wells
37	Sands Point Village.	3002.	Wells
38	Sea Cliff Water Company.	17850.	Wells
39	Sel-Bra Acres Water Supply.	80.	Wells
40	South Farmingdale Water District.	49900.	Wells
41	Split Rock Water Supply.	25.	Wells
42	Uniondale Water District.	25000.	Wells
43	West Hempstead-Hempstead Garden Water District.	32000.	Wells
44	Westbury Water District.	20050.	Wells
45	Williston Park Village.	8216.	Wells

Non-Municipal Community

46	Community Hospital at Glen Cove.	1350.	Wells
47	Planting Fields Arboretum.	90.	Wells
48	Stuart, Walker, Zimmer Water Supply.	41.	Wells

SCALE 1:250,000


5 0 5 MILES



REFERENCE NO. 9



CONTOUR INTERVAL 5 FEET
DATUM IS MEAN SEA LEVEL
DEPTH CURVES AND SOUNDINGS IN FEET - DATUM IS MEAN LOW WATER
SHORELINE SHOWN REPRESENTS THE APPROXIMATE LINE OF MEAN HIGH WATER
THE MEAN RANGE OF TIDE IS APPROXIMATELY 3.9 FEET AT
EAST ROCKAWAY AND 5.4 FEET AT NORTON POINT

	TITLE: THREE MILE VICINITY MAP	
	SITE: AUTOTRONIC PRODUCTS, OCEANSIDE, N.Y.	
DATE: 11/9/87		
TDD: 02-8708-02		
QUAD: LYNBROOK, N.Y.	FIGURE NUMBER:	SCALE: 1" = 2000'

REFERENCE NO. 10

Draft

PROJECT NARRATIVE

WEST HEMPSTEAD BAY

LOCATION AND DESCRIPTION OF HABITAT:

West Hempstead Bay is located along the south shore of Long Island, between the Villages of Lawrence and Island Park, in the Town of Hempstead, Nassau County (7.5' Quadrangles: Lawrence, N.Y.; and Lynbrook, N.Y.). This approximate 4000 acre area is generally defined by the mean high water elevation on the west, north, and east sides, and by the center line of the Reynolds Channel to the south. The fish and wildlife habitat is the entire bay, which includes extensive areas of undeveloped salt marsh, tidal flats, dredge spoil islands, and open water. Water depths in the bay vary from less than 6 feet (below mean low water) in the natural creeks and bays, to over 30 feet in portions of some dredged navigation channels. Tidal fluctuations in the bay average approximately 3.6 - 4.2 feet. West Hempstead Bay is owned by the Town of Hempstead and is managed as a wetland conservation area, with allowance for mosquito control activities (ditching). The bay is surrounded by residential development and small craft harbor facilities.

FISH AND WILDLIFE VALUES:

West Hempstead Bay comprises approximately one-third of the vast Hempstead Bays wetland complex. The bay represents one of the largest undeveloped coastal wetland ecosystems in New York State. This highly diverse area is important to fish and wildlife throughout the year. Common terns (T) nest in many locations throughout the bay, including Hewlett Hassock, Lawrence Marsh, North Green Sedge Island, and Nums Marsh. Approximately 75 pairs of common terns nested in the area during 1984. West Hempstead Bay is also inhabited by a variety of nesting heron species, including snowy egret, great egret, black-crowned night heron, and green-backed heron. This area is also one of the few locations on Long Island where yellow-crowned night heron, tri-colored heron, and little blue heron have been found nesting. Heronries have been located on Pearsall's Hassock, North and South Black Banks Hassock, Lawrence Marsh, North Green Sedge Island, and Boorman's Island. Nests are usually placed in woody vegetation which has become established on abandoned dredge spoil deposits. As of 1977, Pearsall's Hassock contained some of the largest nesting concentrations of snowy egrets, great egrets, and glossy ibis in New York State, with estimates of 227, 30, and 260 pairs, respectively. Other species nesting in West Hempstead Bay include Canada goose, black duck, mallard, herring gull, great black-backed gull, clapper rail, willet, Forster's tern, fish crow, marsh wren, boat-tailed grackle, sharp-tailed sparrow, and seaside sparrow. The salt marshes, intertidal flats, and shallows in this area are used extensively as feeding areas for birds nesting here and for many other species during migration (shorebirds in particular).

West Hempstead Bay is one of the most important waterfowl wintering areas (November - March) on Long Island. Mid-winter aerial surveys of waterfowl abundance for the ten year period 1975-1984 indicate average concentrations of over 3,200 birds in the bay each year (8,325 in peak year), including approximately 2,700 brant (8,325 in peak year), and 345 black ducks (1,150 in peak year), along with lesser numbers of scaup, mallard, Canada goose,

duquaw, bufflehead, and red-breasted merganser. West Hempstead Bay supports one of the largest wintering concentrations of brant in New York State. Waterfowl use of the bay during winter is influenced in part by the extent of ice cover each year. Generally, brant and geese feed in open water areas through midwinter, while later in spring (prior to migration), the birds feed extensively in the salt marshes. Concentrations of waterfowl also occur in the area during spring and fall migrations (March-April and October - November, respectively). All of West Hempstead Bay is open to the public for waterfowl hunting, and the area supports regionally significant hunting pressure.

In addition to having significant bird concentrations, West Hempstead Bay is a productive area for marine finfish, shellfish, and other wildlife. The bay serves as a nursery and feeding area (April - November, generally) for bluefish, winter flounder, summer flounder, kingfish, weakfish, blackfish, snapper, scup, blue claw crabs, and forage species, such as Atlantic silverside, menhaden, pipefish, and sticklebacks. As a result of the abundant fisheries resources in the bay, and its proximity to the New York metropolitan area, West Hempstead Bay receives heavy recreational fishing pressure, of regional significance. The bay is inhabited by hard clams and ribbed mussels, but most of the bay waters are not certified for shellfishing. There is considerable potential for harvesting young clams from the area for transplanting into commercial aquaculture areas. Diamondback terrapin (SC) nest among the salt marsh islands in the bay. Muskrat populations in the area support a significant amount of trapping by local residents.

IMPACT ASSESSMENT:

Any activity that would substantially degrade the water quality in West Hempstead Bay could adversely affect the biological productivity of this area. All species of fish and wildlife may be affected by water pollution, such as chemical contamination (including food chain effects), oil spills, excessive turbidity, and waste disposal. Efforts should be made to improve water quality in the bay, including control of sewage discharges from recreational boats and upland sources. Alteration of tidal patterns in West Hempstead Bay could have major impacts on the fish and wildlife communities present. No new navigation channels should be excavated within the area. Dredging to maintain existing boat channels in the bay should be scheduled in late summer and fall to minimize impacts on aquatic organisms, and to allow for spoil disposal when wildlife populations are least sensitive to disturbance. Elimination of salt marsh and shallow areas, through excavation or filling, would result in a direct loss of valuable habitat area. Unregulated dredge spoil disposal in this area could be detrimental, but such activities may be designed to maintain or improve the habitat for certain species of wildlife. Nesting birds inhabiting the islands of West Hempstead Bay are highly vulnerable to disturbance by humans from mid-April through July. Recreational use (e.g., boat landing, picnicking) of those islands which contain concentrations of nesting birds should be minimized during this period, through the use of annual posting or fencing. Construction and maintenance of shoreline structures, such as docks, piers, bulkheads, or revetments, in areas not previously disturbed by development (i.e., natural salt marsh tidal flats, or shallows), may have a significant impact on the fish and wildlife resources of West Hempstead Bay.

KNOWLEDGEABLE CONTACTS:

Harry Knoch, Wildlife Manager
or Louise Harrison, Environmental Protection Biologist
NYSDEC - Region 1
State University of New York, Building 40
Stony Brook, NY 11790
Phone: (516)751-7900

John Poole, Marine Resources Specialist IV
Bureau of Marine Finfish and Crustaceans
NYSDEC - Region 1
State University of New York, Building 40
Stony Brook, NY 11790
Phone: (516)751-7900

Pieter VanVolkenburgh, Chief
Bureau of Shellfisheries
NYSDEC - Region 1
State University of New York, Building 40
Stony Brook, NY 11790
Phone: (516)751-7900


John Zarudsky, Conservation Biologist
Town of Hempstead
Dept. of Conservation and Waterways
Lido Boulevard, P.O. Box J
Point Lookout, NY 11569
Phone: (516)431-9200

NYSDEC - Significant Habitat Unit
Wildlife Resources Center
Delmar, NY 12054
Phone: (518)439-7486

NAME OF AREA: West Longmead Bay

QUADRANGLE: Lawrence

NEW YORK STATE SIGNIFICANT HABITATS



NAME OF AREA: West Hempstead Bay


QUADRANGLE: Lawrence

PAGE 2 OF 3

NEW YORK STATE SIGNIFICANT HABITATS

7.5 MINUTE SERIES (TOPO)

SW/4 HEMPSTEAD 15' QUADRANT



NAME OF AREA:


West Hempstead Bay

QUADRANGLE:


Lynbrook

PAGE 3 OF 3

NEW YORK STATE SIGNIFICANT HABITATS



SCALE 1:24 000



CONTOUR INTERVAL 5 FEET
DATUM IS MEAN SEA LEVEL

DEPTH CURVES AND SOUNDINGS IN FEET—DATUM IS MEAN LOW WATER
SHORTLINE SHOWN REPRESENTS THE APPROXIMATE LINE OF MEAN HIGH WATER
THE MEAN RANGE OF TIDE IS APPROXIMATELY 3.9 FEET AT
EAST ROCKAWAY AND 5.4 FEET AT NORTON POINT

THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS
FOR SALE BY U.S. GEOLOGICAL SURVEY, WASHINGTON, D. C. 20242
A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST



QUADRANGLE LC

Draft

PROJECT NARRATIVE

MIDDLE HEMPSTEAD BAY

LOCATION AND DESCRIPTION OF HABITAT:

Middle Hempstead Bay ("Middle Bay") is located along the south shore of Long Island, between the Village of Island Park and the Meadowbrook State Parkway, in the Town of Hempstead, Nassau County (7.5' Quadrangles: Freeport, N.Y.; Jones Inlet, N.Y.; Lawrence, N.Y.; and Lynbrook, N.Y.). This approximate 5,000 acre area is generally defined by the mean high water elevation on all sides, except south of the Loop Parkway, where it extends to the center line of the Reynolds and Sloop Channels. The fish and wildlife habitat is the entire bay, which includes extensive areas of undeveloped salt marsh, tidal flats, dredge spoil islands, and open water. Water depths in the bay vary from less than 6 feet (below mean low water) in the natural creeks and bays, to over 30 feet in portions of some dredged navigation channels. Tidal fluctuations in the bay average approximately 3.6 - 4.2 feet. Most of Middle Hempstead Bay is owned by the Town of Hempstead and is managed as a wetland conservation area, with allowance for mosquito control activities (ditching). The bay is surrounded by residential development and small craft harbor facilities, except on the east side, which is bordered by undeveloped right-of-way for the Meadowbrook Parkway.

FISH AND WILDLIFE VALUES:

Middle Hempstead Bay comprises approximately one-third of the vast Hempstead Bays wetland complex. The bay represents one of the largest undeveloped coastal wetland ecosystems in New York State. This highly diverse area is important to fish and wildlife throughout the year. Common terns (T) nest in many locations throughout the bay, including Garrett Marsh, East Channel Islands, North Cinder Island, Gull Island, and Cinder Island. In 1984, a total of approximately 575 pairs of common terns nested in Middle Bay. Middle Bay is also inhabited by a variety of nesting heron species, including snowy egret, great egret, black-crowned night heron, and green-backed heron. This area is also one of the few locations on Long Island where yellow-crowned night heron and tri-colored heron have been found nesting. Heronries have been located on South Pine Marsh, High Meadow Island, and on Smith Meadow, south of Little Swift Creek. Nests are usually placed in woody vegetation which has become established on abandoned dredge spoil deposits. As of 1977, Smith Meadow contained regionally significant nesting concentrations of snowy egret, black-crowned night heron, and glossy ibis, with estimates of 165, 95, and 53 pairs, respectively. Other species nesting in Middle Hempstead Bay include Canada goose, black duck, mallard, herring gull, American oystercatcher, clapper rail, willet, gull-billed tern, fish crow, marsh wren, sharp-tailed sparrow, and seaside sparrow. The salt marshes, intertidal flats, and shallows in this area are used extensively as feeding areas for birds nesting here and for many other species during migration (shorebirds in particular).

Middle Hempstead Bay is one of the most important waterfowl wintering areas (November - March) on Long Island. Mid-winter aerial surveys of waterfowl abundance for the ten year period 1975-1984 indicate average

concentrations of over 6,600 birds in the bay each year (26,855 in peak year), including approximately 4,200 brant (10,880 in peak year), 2,000 scaup (17,750 in peak year), and 230 black ducks (975 in peak year), along with lesser numbers of bufflehead, common goldeneye, canvasback, mallard, Canada goose, oldsquaw, and red-breasted merganser. Middle Bay supports the largest wintering concentration of brant in New York State. Waterfowl use of the bay during winter is influenced in part by the extent of ice cover each year. Generally, brant and geese feed in open water areas through midwinter, while later in spring (prior to migration), the birds feed extensively in the salt marshes. Concentrations of waterfowl also occur in the area during spring and fall migrations (March - April and October - November, respectively). All of Middle Bay is open to the public for waterfowl hunting, and the area supports regionally significant hunting pressure.

In addition to having significant bird concentrations, Middle Hempstead Bay is a productive area for marine finfish, shellfish, and other wildlife. The bay serves as a nursery and feeding area (from April - November, generally) for bluefish, winter flounder, summer flounder, kingfish, weakfish, blackfish, scup, blue claw crab, and forage fish species, such as Atlantic silverside, pipefish, and sticklebacks. As a result of the abundant fisheries resources in the bay, and its proximity to the New York metropolitan area, Middle Bay receives heavy recreational fishing pressure, of regional significance. The bay is inhabited by hard clams and ribbed mussels, but most of the bay waters are not certified for shellfishing. There is considerable potential for harvesting young clams from the area for transplanting into commercial aquaculture areas. Diamondback terrapin (SC) nest among the salt marsh islands in the bay, and at the Oceanside Marine Nature Study Area. Muskrat populations in the area support a significant amount of trapping by local residents. Several facilities for environmental education are located around Middle Bay, providing nature study opportunities for many Nassau County residents.

IMPACT ASSESSMENT:

Any activity that would substantially degrade the water quality in Middle Hempstead Bay could adversely affect the biological productivity of this area. All species of fish and wildlife may be affected by water pollution, such as chemical contamination (including food chain effects), oil spills, excessive turbidity, and waste disposal. Efforts should be made to improve water quality in the bay, including control of sewage discharges from recreational boats and upland sources. Alteration of tidal patterns in Middle Bay could have major impacts on the fish and wildlife communities present. No new navigation channels should be excavated within the area. Dredging to maintain existing boat channels in the bay should be scheduled in late summer and fall to minimize potential impacts on aquatic organisms, and to allow for spoil disposal when wildlife populations are least sensitive to disturbance. Elimination of salt marsh and shallow areas, through excavation or filling, would result in a direct loss of valuable habitat area. Unregulated dredge spoil disposal in this area could be detrimental, but such activities may be designed to maintain or improve the habitat for certain species of wildlife. Nesting birds inhabiting the islands of Middle Bay are highly vulnerable to disturbance by humans from mid-April through July. Recreational use (e.g., boat landing, picnicking) of those islands which contain concentrations of nesting birds should be minimized during this period, through the use of annual posting or fencing. Construction and maintenance of shoreline structures, such as docks, piers, bulkheads, or revetments, in areas not

previously disturbed by development (i.e., natural salt marsh, tidal flats, or shallows), may have a significant impact on the fish and wildlife resources of Middle Hempstead Bay.

KNOWLEDGEABLE CONTACTS:

Harry Knoch, Wildlife Manager
or Louise Harrison, Environmental Protection Biologist
NYSDEC - Region 1
State University of New York, Building 40
Stony Brook, NY 11790
Phone: (516)751-7900

John Poole, Marine Resources Specialist IV
Bureau of Marine Finfish and Crustaceans
NYSDEC - Region 1
State University of New York, Building 40
Stony Brook, NY 11790
Phone: (516)751-7900

Pieter VanVolkenburgh, Chief
Bureau of Shellfisheries
NYSDEC - Region 1
State University of New York, Building 40
Stony Brook, NY 11790
Phone: (516)751-7900

John Zarudsky, Conservation Biologist
Town of Hempstead
Dept. of Conservation and Waterways
Lido Boulevard, P.O. Box J
Point Lookout, NY 11569
Phone: (516)431-9200

NYSDEC-Significant Habitat Unit
Wildlife Resources Center
Delmar, NY 12054
Phone: (518)439-7486

NAME OF AREA: *Long Beach*

QUADRANGLE: *Long Beach*


PAGE 1 OF 1

NEW YORK STATE SIGNIFICANT HABITATS



1 MI. TO INTERCHANGE M 10 (JONES INLET)
JONES INLET 4 MI. 6265 11 SE

SCALE 1:24000



CONTOUR INTERVAL 5 FEET

NAME OF AREA:


Middle Longstead Bay

QUADRANGLE:

Long Island

PAGE 3 OF 5

NEW YORK STATE SIGNIFICANT HABITATS



NAME OF AREA: Hempstead Bay

QUADRANGLE: Hempstead Bay

PAGE 4 OF 5

NEW YORK STATE SIGNIFICANT HABITATS



Draft

PROJECT NARRATIVE

NASSAU BEACH

LOCATION AND DESCRIPTION OF HABITAT:

Nassau Beach is located approximately one mile west of Point Lookout, on the westernmost barrier island on Long Island's south shore. The beach is located within Nassau Beach County Park, in the Town of Hempstead, Nassau County (7.5' Quadrangle: Jones Inlet, N.Y.). The fish and wildlife habitat consists of approximately 15 acres of sparsely vegetated dunes and the adjoining shell and pebble beach. The area is subdivided by sections of snow fence which extend from the upper beach into the dunes, perpendicular to the shoreline. Although the beach receives heavy recreational use during the summer, the habitat area is generally located behind the open beach, and receives relatively little human disturbance. The area was not posted or fenced as a bird nesting area in 1984.

FISH AND WILDLIFE VALUES:

The Nassau Beach fish and wildlife habitat consists of a small segment of undeveloped barrier beach ecosystem. Development and use of the adjacent recreation facilities has resulted in relatively little degradation of the habitat. Areas such as this are rare in Nassau County. Nassau Beach serves as an important nesting site for least terns (E) and piping plovers (T). From 1982-1984, approximately 100-160 pairs of least terns and 1-3 pairs of piping plovers have nested in the area. The least tern populations at this site in 1983 and 1984 were the largest in Nassau County, and were among the ten largest on Long Island in those years. There are no significant human use activities associated with the wildlife resources at Nassau Beach.

IMPACT ASSESSMENT:

Nesting shorebird species inhabiting the barrier beaches of Long Island are highly vulnerable to disturbance by humans from mid-April through July. Significant pedestrian traffic or recreational use of the uppermost beach area and dunes could destroy the Nassau Beach tern and plover nesting habitat, and should be minimized during this period. Fencing and/or annual posting of the bird nesting area should be provided to help protect the nesting bird species. Unregulated dredge spoil disposal in this area could be detrimental, but such activities may be designed to maintain or improve the habitat, by setting back vegetative succession. Introduction or attraction of mammalian predators to the Nassau Beach area would also be detrimental to the populations of nesting birds.

KNOWLEDGEABLE CONTACTS:

Harry Knoch, Wildlife Manager
or Louise Harrison, Environmental Protection Biologist
NYSDEC - Region 1
State University of New York, Building 40
Stony Brook, NY 11790
Phone: (516)751-7900


John Zarudaky, Conservation Biologist
Town of Hempstead
Dept. of Conservation and Waterways
Lido Boulevard, P.O. Box J
Point Lookout, N.Y. 11569
Phone: (516)431-9200

David Peterson, Staff Biologist
Seatuck Research Program
Cornell University Laboratory of Ornithology
P.O. Box 31
Islip, N.Y. 11751
Phone: (516)581-6908

NYSDEC-Significant Habitat Unit
Wildlife Resources Center
Delmar, NY 12054
Phone: (518)439-7486

NEW YORK STATE SIGNIFICANT HABITATS

LAWRENCE QUADRANGLE
NEW YORK
7.5 MINUTE SERIES (TOPOGRAPHIC)
SW/4 HEMPSTEAD 15' QUADRANGLE



REFERENCE NO. 11

AUTOTRONIC PRODUCTS

Lat: 40°37'46"N

Long: 73°39'13"W

Data List of Dataset: NYW3

Number of Records = 6

REC #	POP	HOUSE	DISTANCE	SECTOR
1	650	197	0.400000	1
2	4728	1464	0.810000	1
3	7779	2579	1.60000	1
4	50696	17151	3.20000	1
5	85551	28703	4.80000	1
6	111423	39336	6.40000	1

	1/4	1/2	1	2	3	4
Population	650	5378	13,57	63,853	149,404	260,827
Housing	197	1661	4240	21,391	50,094	89,430

REFERENCE NO. 12

**CHEMICAL, PHYSICAL, AND BIOLOGICAL
PROPERTIES OF COMPOUNDS PRESENT
AT HAZARDOUS WASTE SITES**

Final Report

Prepared for:

U.S. Environmental Protection Agency

Prepared by:

**Clement Associates, Inc.
1515 Wilson Boulevard
Arlington, Virginia 22209**

Under Subcontract to:

**GCA Corporation
Bedford, Massachusetts 01730**

September 27, 1985

1,1,1-TRICHLOROETHANE

Summary

Preliminary results suggest that 1,1,1-trichloroethane (1,1,1-TCA) induces liver tumors in female mice. It was shown to be mutagenic using the Ames assay, and it causes transformation in cultured rat embryo cells. Inhalation exposure to high concentrations of 1,1,1-TCA depressed the central nervous system; affected cardiovascular function; and damaged the lungs, liver, and kidneys in animals and humans. Irritation of the skin and mucous membranes has also been associated with human exposure to 1,1,1-trichloroethane.

CAS Number: 71-55-6

Chemical Formula: CH_3CCl_3

IUPAC Name: 1,1,1-Trichloroethane

Important Synonyms and Trade Names: Methyl chloroform, chloro-
thene, 1,1,1-TCA

Chemical and Physical Properties

Molecular Weight: 133.4

Boiling Point: 74.1°C

Melting Point: -30.4°C

Specific Gravity: 1.34 at 20°C (liquid)

Solubility in Water: 480-4,400 mg/liter at 20°C (several divergent values were reported in the literature)

Solubility in Organics: Soluble in acetone, benzene, carbon tetrachloride, methanol, ether, alcohol, and chlorinated solvents

Log Octanol/Water Partition Coefficient: 2.17

Vapor Pressure: 123 mm Hg at 20°C

Vapor Density: 4.63

Transport and Fate

1,1,1-Trichloroethane (1,1,1-TCA) disperses from surface water primarily by volatilization. Several studies have indicated that 1,1,1-trichloroethane may be adsorbed onto organic materials in the sediment, but this is probably not an important route of elimination from surface water. 1,1,1-Trichloroethane can be transported in the groundwater, but the speed of transport depends on the composition of the soil.

Photooxidation by reaction with hydroxyl radicals in the atmosphere is probably the principal fate process for this chemical.

Health Effects

1,1,1-Trichloroethane was retested for carcinogenicity because in a previous study by NCI (1977), early lethality precluded assessment of carcinogenicity. Preliminary results indicate that 1,1,1-TCA increased the incidence of combined hepatocellular carcinomas and adenomas in female mice when administered by gavage (NTP 1984). There is evidence that 1,1,1-trichloroethane is mutagenic in Salmonella typhimurium and causes transformation in cultured rat embryo cells (USEPA 1980). These data suggest that the chemical may be carcinogenic.

Other toxic effects of 1,1,1-TCA are seen only at concentrations well above those likely in an open environment. The most notable toxic effects of 1,1,1-trichloroethane in humans and animals are central nervous system depression, including anesthesia at very high concentrations and impairment of coordination, equilibrium, and judgment at lower concentrations (350 ppm and above); cardiovascular effects, including premature ventricular contractions, decreased blood pressure, and sensitization to epinephrine-induced arrhythmia; and adverse effects on the lungs, liver, and kidneys. Irritation of the skin and mucous membranes resulting from exposure to 1,1,1-trichloroethane has also been reported. The oral LD₅₀ value of 1,1,1-trichloroethane in rats is about 11,000 mg/kg.

Toxicity to Wildlife and Domestic Animals

The acute toxicity of 1,1,1-trichloroethane to aquatic species is rather low, with the LC₅₀ concentration for the most sensitive species tested being 52.8 mg/l. No chronic toxicity studies have been done on 1,1,1-trichloroethane, but acute-chronic ratios for the other chlorinated ethanes ranged from 2.8 to 8.7. 1,1,1-Trichloroethane was only slightly bioaccumulated with a steady-state bioconcentration factor of nine and an elimination half-life of two days.

No information on the toxicity of 1,1,1-trichloroethane to terrestrial wildlife or domestic animals was available in the literature reviewed.

Regulations and Standards

Ambient Water Quality Criteria (USEPA):

Aquatic Life

The available data are not adequate for establishing criteria. However, EPA did report, the lowest values of the two trichloroethanes (1,1,1 and 1,1,2) known to be toxic in aquatic organisms.

Freshwater

Acute toxicity: 18 mg/liter
Chronic toxicity: 8.4 mg/liter

Saltwater

Acute toxicity: 31.2 mg/liter
Chronic toxicity: No available data

Human Health

Criterion: 18.4 mg/liter

NIOSH Recommended Standard: 350 ppm (1,910 mg/m³)/15 min Ceiling Level

OSHA Standard: 350 ppm (1,910 mg/m³) TWA

REFERENCES

INTERNATIONAL AGENCY FOR RESEARCH ON CANCER (IARC). 1979. IARC Monographs on the Evaluation of the Carcinogenic Risks of Chemicals to Humans. Vol. 20: Some Halogenated Hydrocarbons. World Health Organization, Lyon, France. Pp. 515-531

NATIONAL CANCER INSTITUTE (NCI). 1977. Bioassay of 1,1,1-Trichloroethane for Possible Carcinogenicity. CAS No. 71-55-6. NCI Carcinogenesis Technical Report Series No. 3. Washington, D.C. DHEW Publication No. (NIH) 77-803

NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY AND HEALTH (NIOSH).
1976. Criteria for a Recommended Standard--Occupational
Exposure to 1,1,1-Trichloroethane (Methyl Chloroform).
Washington, D.C. DHEW Publication No. (NIOSH) 76-184

NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY AND HEALTH (NIOSH).
1983. Registry of Toxic Effects of Chemical Substances.
Data Base. Washington, D.C. October 1983

NATIONAL TOXICOLOGY PROGRAM (NTP). 1984. Annual Plan for
Fiscal Year 1984. Research Triangle Park, N.C. DHHS
Public Health Service. NTP-84-023

U.S. ENVIRONMENTAL PROTECTION AGENCY (USEPA). 1979. Water-
Related Environmental Fate of 129 Priority Po -ants.
Washington, D.C. December 1979. EPA 440/4- 29

U.S. ENVIRONMENTAL PROTECTION AGENCY (USEPA). 1 Ambient
Water Quality Criteria for Chlorinated Eth- Office
of Water Regulations and Standards, Criteria and Standards
Division, Washington, D.C. October 1980. EPA 440/5-80-029


U.S. ENVIRONMENTAL PROTECTION AGENCY (USEPA). 1984. Health
Effects Assessment for 1,1,1-Trichloroethane. Environmental
Criteria and Assessment Office, Cincinnati, Ohio. September
1984. ECAO-CIN-H005 (Final Draft)

VERSCHUEREN, K. 1977. Handbook of Environmental Data on Organic
Chemicals. Van Nostrand Reinhold Co., New York. 659 pages

WEAST, R.E., ed. 1981. Handbook of Chemistry and Physics.
62nd ed. CRC Press, Cleveland, Ohio. 2,332 pages

REFERENCE NO. 13

KEY TO MAP

500-Year Flood Boundary	—
100-Year Flood Boundary	—
Zone Designations*	
100-Year Flood Boundary	—
500-Year Flood Boundary	—
Base Flood Elevation Line With Elevation In Feet**	—513—
Base Flood Elevation in Feet Where Uniform Within Zone**	(E1.9871)
Elevation Reference Mark	RM7
Zone D Boundary	—
River Mile	•M1.5

**Referenced to the National Geodetic Vertical Datum of 1929

*EXPLANATION OF ZONE DESIGNATIONS

ZONE	EXPLANATION
A	Areas of 100-year flood; base flood elevations and flood hazard factors not determined.
A0	Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; average depths of inundation are shown, but no flood hazard factors are determined.
AH	Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; base flood elevations are shown, but no flood hazard factors are determined.
A1 A30	Areas of 100-year flood; base flood elevations and flood hazard factors determined.
A99	Areas of 100-year flood to be protected by flood protection system under construction; base flood elevations and flood hazard factors not determined.
B	Areas between limits of the 100-year flood and 500-year flood; or certain areas subject to 100-year flooding with average depths less than one (1) foot or where the contributing drainage area is less than one square mile; or areas protected by levees from the base flood. (Medium shading)
C	Areas of minimal flooding. (No shading)
D	Areas of undetermined, but possible, flood hazards.
V	Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors not determined.
V1 V30	Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors determined.

NOTES TO USER

Certain areas not in the special flood hazard areas (zones A and V) may be protected by flood control structures.

This map is for flood insurance and flood plain management purposes only; it does not necessarily show all areas subject to flooding in the community or all planimetric features outside special flood hazard areas. The coastal flooding elevations shown may differ significantly from those developed by the National Weather Service for hurricane evacuation planning.

For adjoining map panels, see separately printed Index To Map Panels.

Coastal base flood elevations shown on this map include the effects of wave action.

Coastal base flood elevations apply only landward of 0.0 NGVD.

INITIAL IDENTIFICATION:
APRIL 26, 1975

FLOOD HAZARD BOUNDARY MAP REVISIONS:
NONE


FLOOD INSURANCE RATE MAP EFFECTIVE:
APRIL 16, 1979

FLOOD INSURANCE RATE MAP REVISIONS:
March 4, 1985 to include the effects of wave action

To determine if flood insurance is available in this community, contact your insurance agent, or call the National Flood Insurance Program, at (800) 638-6620.



APPROXIMATE SCALE



NATIONAL FLOOD INSURANCE PROGRAM

FIRM FLOOD INSURANCE RATE MAP

TOWN OF
HEMPSTEAD,
NEW YORK
NASSAU COUNTY

PANEL 51 OF 75


(SEE MAP INDEX FOR PANELS NOT PRINTED)

COMMUNITY-PANEL NUMBER
360467 0051 B

MAP REVISED:
MARCH 4, 1985



Federal Emergency Management Agency



REFERENCE NO. 14

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE


PRIME FARMLAND OF NEW YORK

INTERPRETATIONS DERIVED FROM GENERAL SOIL MAP COMPILED BY CORNELL UNIVERSITY AGRICULTURAL EXPERIMENT STATION
CONSTRUCTED 1977 BY CARTOGRAPHIC DIVISION, SOIL CONSERVATION SERVICE, U.S. DEPARTMENT OF AGRICULTURE


AUGUST 1979

Scale 1: 750,000

1 Inch Equals Approximately 12 Miles



Source Data: U.S. Geological Survey 1:500,000 Base Map



LEGEND

Map Symbol

Name

1. Glacial Till

A - *Hapludalfs* dominant

- A1 Cazenovia and Mohawk areas
- A2 Hilton areas
- Honeoye areas
- A4 Lansing areas
- Madrid areas
- A6 Ontario areas

Aw - *Ochraqualls* dominant

- Aw1 Appleton areas
- Aw2 Burdett and Darien areas
- Aw3 Ovid areas

B - *Fragiudalfs* dominant

- B Langford areas

Bw - *Fragiaqualls* dominant

- Bw Erie areas

C - *Eutrochrepts* dominant

- C Nellis areas
- Cr Farmington areas
- CLw1 Hogansburg-Swanton areas
- CLw2 Pittsfield-Rhinebeck areas

D - *Dystrochrepts* dominant

- D Charlton areas
- Dh Muskingum areas
- DhE Lordstown-Mardin areas
- Dr1 Hollis areas
- Dr2 Lordstown and Oquaga areas
- Dr3 Nassau areas
- Ds Charlton, Paxton, and Essex areas.

Dw - *Haplaquepts* dominant

- Dw Fremont and Hornell areas

E - *Fragiochrepts* dominant

- E1 Bath areas
- E2 Ira areas
- E3 Lackawanna areas
- E4 Mardin areas
- E5 Sodus areas
- EDr Bernardston-Nassau areas
- EG Bernardston-Hoosic areas
- Es Lackawanna and Wurtsboro areas, very stony

Ew - *Fragiaquepts* dominant

- Ew1 Mosherville areas
- Ew2 Volusia areas

F - *Haplorthods*, *Fragiorthods*, or very stony *Fragiaquods* dominant

- F Empeyville areas
- Fs1 Becket, Berkshire, and Potsdam areas, very stony
- Fs2 Westbury and Coveytown areas, very stony

Fs3 Worth areas, very stony

Fw - *Fragiaquods* and *frigid Fragiaquepts* dominant

Fw1 Camroden areas

Fw2 Westbury and Brayton areas

2. Glacial Outwash and Deltaic Sand

G - *Dystrochrepts* dominant

- Chenango and Blasdell areas
- Haven and Riverhead areas
- GD Chenango-Valois and Howard-Madrid areas

Gd - *Udipsamments*, *sandy skeletal Dystrochrepts* or *skeletal Eutrochrepts* dominant

- Gd1 Alton and Hoosic areas
- Gd2 Colonie, Plymouth and Windsor areas
- GdE Plymouth-Montauk areas

Gw - *Psammaquepts* or *Haplaquepts* dominant

- Gw Minoa and Stafford areas

H - *Hapludalfs* dominant

- H1 Arkport areas
- Howard areas
- Palmyra areas

Kd - *Haplorthods* dominant

- Kd Colton and Adams areas

Kw - *Haplaquods* dominant

- Kw Naumburg areas

3. Lake and Marine Sediments

L - *Hapludalfs* or *silty Fragiochrepts* dominant

- Collamer areas
- L2 Schoharie areas
- LE Williamson-Ira areas
- Lh Hudson areas

Lw - *Ochraqualls* or *Haplaquepts* dominant

- Lw1 Canandaigua areas
- Lw2 Kingsbury areas
- Niagara areas
- Lw4 Odessa and Rhinebeck areas
- Lw5 Swanton-Rhinebeck areas
- LwC Kingsbury-Hogansburg areas
- LwR Kingsbury-Rock outcrop areas

4. Organic Deposits

M - *Histosols* dominant

- Carlisle and Palms areas

5. Miscellaneous Units

R - *Rock outcrop* dominant

- R Rock outcrop areas, sloping
- Rh Rock outcrop areas, steep

U - *Unclassified soil*

- U1 Beach-Tidal marsh areas
- U2 Urban Land areas

LEGEND

Prime Farmland Defined By USDA - SCS

 MORE THAN 75 PERCENT PRIME FARMLAND

 25 PERCENT TO 75 PERCENT PRIME FARMLAND

 LESS THAN 25 PERCENT PRIME FARMLAND

 URBAN AREAS

SPOT SYMBOLS

 Very stony soils

 Wet soils

 Organic soils

 Sandy soils

 Rock outcrops

 Soils in outwash or alluvium

 Gravelly soils

 Soils on glacial lake beaches

45'

30'


15'

76°

45'

30'

15'



- Lw1 Canandaigua areas
- Lw2 Kingsbury areas
- Niagara areas
- Lw4 Odessa and Rhinebeck areas
- Lw5 Swanton-Rhinebeck areas
- LwC Kingsbury-Hogansburg areas
- LwR Kingsbury-Rock outcrop areas

4. Organic Deposits

M - Histosols dominant

 Carlisle and Palms areas

5. Miscellaneous Units

R - Rock outcrop dominant

R Rock outcrop areas, sloping

Rh Rock outcrop areas, steep

U - Unclassified soil

U1 Beach-Tidal marsh areas

U2 Urban Land areas

A T L A N T I C

75° 74° 45' 30' 15' 73° 45' 30'

REFERENCE NO. 15

Autotronic
PRODUCTS, INC.

3300 Lawson Blvd., Oceanside, N.Y. 11572
Telephone: 516-536-6765

June 24, 1987

Nassau County
Department of Health
240 Old Country Rd
Mineola, NY 11501
Att: Mr. Howard Schaefer

RE: Nassau County Public Health
Ordinance

Dear Mr. Schaefer:


Attached please find our application for a permit to operate a hazardous material storage facility.

We have enclosed Form 1 and Form 3 including a plot plan since we only store one (1) 55 gal drum at a time.

In fact, we have for the last twelve months less than ten (10) gallons of waste on-site due to a change in our use requirements and generally business slowdown.

We believe that the information is adequate to allow the county to renew our permit.

Very truly yours,


Joseph M. Spadafina
President

JMS:js

RECEIVED

For Office Use Only
Facility 1.12

JUN 29 1987

NASSAU COUNTY DEPARTMENT OF HEALTH
APPLICATION FOR A TOXIC OR HAZARDOUS MATERIALS STORAGE FACILITY PERMIT
1 - GENERAL INFORMATION
INSTRUCTION SHEET

NCDH - BLRM

Check all that apply
to your facility:

☐ Tank Storage

☒ Container Storage

☐ Bulk Storage

☐ Storage of Road De-icing Materials

Reason for submitting application:

☐ New

☐ Renewal

☐ Change

☐ Construction

Facility Name
Autotronic Products Inc.

Street Address
3300 Lawson Blvd.

Village
Oceanside

State
NY

Zip
11572

Phone
16-536-6765

Facility Mailing Address (If different from above)
Same

Facility Contact Person (Name & Title)
Joseph M. Spadafina,
President

Phone
"-536-6765

Facility Owner
Autotronic Products, Inc.

Street Address
3300 Lawson Blvd.

Village
Oceanside

State
NY

Zip
11572

Phone
"-536-6765

Property Owner (If not Facility Owner)
Joseph M. Spadafina

Street Address
224 Windsor Lane

Village
W. Hempstead

State
NY

Zip
11552

Phone
"-538-2147

Tank Owner (If not Facility Owner)
N/A

Street Address

Village

State

Zip

Phone

Name that should appear on Permit (Permittee)
(If different from Facility Owner)

Permittee's Street Address
3300 Lawson Blvd.

Village
Oceanside

State
NY

Zip
11572

Phone
16-536-6765

Permittee's Relationship
to Facility Owner:

☒ Same

☐ Operator of Facility

☐ Other (Specify):

Principal Property Tax Code:

School District No.
011

Section
43

Block
380

Lot
274-290

Forms Attached

☐ Form 2 - Tank Registration

☒ Form 3 - Bulk & Container
Storage Registration

☐ Form 4 - Storage of Road
De-icing Materials

Check all that apply)

I hereby affirm under penalty of perjury that the information provided on this form and on any attached forms,
statements and exhibits is true to the best of my knowledge and belief.

Signature

REFERENCE NO. 16

TO: Autotronic Products File DATE: 09/04/87
FROM: W. Schnitzerling COPIES:
SUBJECT: Groundwater Usage Near This Site (Oceanside, Nassau County, NY)
REFERENCE: Mr. D. Myatt - Nassau County Health Department - Pure Waters Division

Mr. Myatt is responsible for ensuring the public receives potable water. He was very familiar with the Autotronic Products site.

Drinking Water: All the drinking water within three miles of this site is drawn from the Magathy, although there are three aquifers underlying this site; the Glacial, the Magathy and the Llyod. The shallow Glacial Aquifer is not used for drinking. It has been partially contaminated, because it is so shallow. (In several areas depth to groundwater is ^{only} only a few feet). Although the Glacial Aquifer is not used as a drinking water source, many Long Island residents have private wells. These wells are used for irrigation, car washing and other general purposes, but not for drinking. These private wells are used because supplied water is very expensive. (The Long Island Water Company supplies water for this area). The depth to the Magathy Aquifer is approximately 500 feet. This groundwater flows south towards the bays (ocean). The ^{also} Llyod Aquifer is beneath the Magathy. At this time the ^{also} Llyod is not a drinking water source for this area.

The nearest drinking water source is a well 2.5 miles northeast of this site. It is a cluster of 3 wells, designated #50 rd by the Nassau County Health Department (NC HD). The well cluster supplies the village of Rockville Center with potable water. Mr. Myatt estimated, there are over 29,000 residents of this village. There are no drinking water sources ^{and} south of this site, all the drinking water wells are north of this site.

The nearest well (designated #5483 by the NC HD) is located one half mile from Autotronic Products. It is 55 feet deep and ^{covered}

located by Oceanside School #8. According to Mr. Myatt, this well is used for ~~water~~ irrigation only, not drinking water.

There are no drinking water sources ~~not~~^{not} from surface water intakes, within three miles of this site. The only ~~only~~^{only} surface nearest surface water flows past a huge landfill.

Mr. Myatt said the area surrounding ~~the~~^{the} Datatronix Products is a discharge area. Groundwater does not recharge here. The majority of the water flows (runs-off) into the several bays in this section of Long Island.

REFERENCE NO. 17

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

DATE:

5/10/88

TIME:

1410

DISTRIBUTION:

Autotronic Products

02-8708-02-\$I

NYW3\$I 325
NY300\$I

BETWEEN:

D. MYOTT

OF:

Nassau County
Health Dept.
Pure H₂O Div.

PHONE:

(516) 535-2201

AND:

STANLEY SULFER, ENVIRON. SCIENTIST

DISCUSSION:

I advised Mr. Myott that I wished to clarify some information from the ~~the~~ interview of 9/4/87 with Mr. Schmitzling.

1. Depth to ground water in Upper Glacial aquifer. Mr. Myott stated it runs about 5 ft. below the surface of the ground.

2. Use of ~~upper~~ upper glacial ^{aquifer} water for irrigation. Mr. Myott stated due to the shallow depth to ground water many homeowners install their own irrigation wells by driving well points. No records of these wells exist, unless permit was obtained

ACTION ITEMS:

from NYS DEC. Permits required for well drawing greater than 45 gpm. Contact NYSDEC at:

NYS DEC

Stony Brook, NY

516-751-7900 ask for George Schilpp

over →

2 cont. Mr. Myott stated that every home in the area has the potential to tap the Upper Glacial aquifer in this manner.

3. Are the Upper Glacial and Magothy aquifers connected? Mr. Myott stated that in theory they are connected, however the large depth to the Magothy aquifer (2500ft) does cause these waters to act in an artesian manner. Therefore if there were any connection with these aquifers it would be Magothy to the Upper Glacial Aquifer. The Upper Glacial aquifer discharges to the bay. For further info., Mr. Myott recommended contacting the USGS which has studied the aquifers of L.I. extensively. I advised Mr. Myott I have already read several of their reports as background information.

Stanley B. Muhl

REFERENCE NO. 18

New York

48072-A1-EI-250

N. Y.—CONN.—N. J.

1:250 000-scale map of Atlantic Coast Ecological Inventory



Produced by
U. S. FISH AND WILDLIFE
SERVICE
1980

TERRESTRIAL ORGANISMS

Shown in BROWN: species with special status shown in RED-(F) or (S) indicates species protected by Federal or State Legislation (see text)

SYMBOL

SPECIES

PLANTS (301-350)

- 301 Eastern hemlock
- 302 Spleenwort (S)
- 303 Spider lily (S)
- 304 Pond bush (S)
- 305 Watermilfoil (S)
- 306 Hooded pitcher plant (S)
- 307 Tree
- 308 Prickly pear cactus (S)
- 309 Trailing arbutus (S)
- 310 Eastern bumelia
- 311 Pitcher plant
- 312 Baldcypress
- 313 Redbay
- 314 Seaside alder
- 315 Box huckleberry
- 316 Purple fringed orchid
- 317 Pink lady's slipper
- 318 Ebony spleenwort (S)
- 319 Orchids (S)
- 320 Golden club (S)
- 321 Florida beargrass
- 322 East-coast coontie
- 323 Fall-flowering ixia
- 324 Jackson-vine
- 325 Spoon-flower
- 326 Curtiss milkweed
- 327 Sea lavender
- 328 Hand fern
- 329 Needle palm
- 330 Yellow squirrel-banana
- 331 Beach creeper
- 332 Florida coontie
- 333 Four-petal pawpaw
- 334 Bird's nest spleenwort
- 335 Burrowing four-o'clock
- 336 Beach star
- 337 Silver palm
- 338 Dancing lady orchid
- 339 Tamarindillo
- 340 Fuch's bromeliad
- 341 Everglades peperomia
- 342 Buccaneer palm
- 343 Slender spleenwort
- 344 Pineland jacquemontia
- 345 Mahogany mistletoe
- 346 Florida thatch
- 347 Twisted air plant
- 348 Long's bittercress
- 349 Venus's flytrap

INVERTEBRATES (351-400)

- 351 Monarch butterfly
- 352 Zebra butterfly

BIRDS (401-600)

SHOREBIRDS (401-430)

- 401 Shorebirds
- 402 Terns
- 403 Gulls
- 404 Forster's tern
- 405 Arctic tern
- 406 Least tern (S)
- 407 Roseate tern (S)
- 408 Common tern
- 409 Great black-backed gull
- 410 Herring gull
- 411 Laughing gull
- 412 Black skimmer (S)
- 413 Turnstones
- 414 Plovers
- 415 Piping plover
- 416 American oystercatcher (S)

- 431 Mating birds
- 432 Egrets
- 433 Rails
- 434 Ibises
- 435 Bitterns
- 436 Great blue heron (S)
- 437 Wood ibis (S)
- 438 Anhinga
- 439 Little blue heron (S)
- 440 Yellow-crowned night heron (S)
- 441 Black-crowned night heron
- 442 Florida sandhill crane (S)
- 443 Louisiana heron (S)
- 444 Limpkin (S)
- 445 Roseate spoonbill (S)
- 446 Snowy egret (S)
- 447 Magnificent frigate-bird (S)
- 448 Reddish egret (S)
- 449 Clapper rail
- 450 King rail
- 451 Virginia rail
- 452 Sora rail

WATERFOWL (461-500)

- 461 Waterfowl
- 462 Swans
- 463 Geese
- 464 Dabbling ducks
- 465 Diving ducks
- 466 Common eider
- 467 Harlequin duck
- 468 Wood duck
- 469 Fulvous tree duck
- 470 Loons
- 471 Grebes
- 472 Brant geese
- 473 Snow goose
- 474 Gadwall
- 475 Black duck

RAPTORS (501-530)

- 501 Raptors
- 502 Owls
- 503 Kites
- 504 Hawks
- 505 Bald eagle (F)
- 506 Osprey (S)
- 507 Peregrine falcon (F)
- 508 Copper's hawk (S)
- 509 Swallow-tailed kite
- 510 Marsh hawk (S)
- 511 Southeastern American kestrel (S)
- 512 Florida burrowing owl (S)

SEABIRDS (531-550)

- 531 Seabirds
- 532 Petrels, shearwaters, and albatrosses
- 533 Pelican and allies
- 534 Alcids
- 535 Brown pelican (F)
- 536 Black guillemot
- 537 Leach's petrel
- 538 Razorbill
- 539 Common puffin
- 540 Double-crested cormorant
- 541 Gannet
- 542 Wilson's petrel
- 543 Northern phalarope
- 544 Audubon's shearwater
- 545 Greater shearwater
- 546 Shearwaters
- 547 Petrels
- 548 Jaegers
- 549 White pelican

SONGBIRDS AND OTHERS (551-600)

- 551 Songbirds and others
- 552 Red-cockaded woodpecker (F)
- 553 Chachalaca
- 554 Bachman's warbler (F)
- 555 Wild turkey
- 556 American woodcock
- 557 Pileated woodpecker
- 558 Swainson's warbler
- 559 Ruffed grouse
- 560 Bobwhite
- 561 Mourning dove
- 562 Warblers
- 563 Ring-necked pheasant
- 564 Bank swallow

REPTILES AND AMPHIBIANS (601-700)

- 601 Eastern narrow-mouthed toad (S)
- 602 Eastern indigo snake (F)
- 603 American alligator (F)
- 604 Northern diamondback terrapin
- 605 Amphibians
- 606 Greater siren
- 607 Bog turtle (S)
- 608 Gopher tortoise (S)
- 609 Eastern tiger salamander (S)
- 610 Northern fence lizard
- 611 Five-lined skink
- 612 Map turtle
- 613 Plymouth red-bellied turtle (F)
- 614 Eastern diamondback rattlesnake
- 615 Carolina gopher frog
- 616 Florida gopher frog (S)
- 617 Atlantic salt marsh watersnake (F)
- 618 American crocodile (F)
- 619 Florida Keys mole skink (S)
- 620 Florida black-headed snake (S)
- 621 Pine barrens tree frog (S)
- 622 Northern pine snake (S)
- 623 Corn snake (S)
- 624 Timber rattlesnake (S)
- 625 Southern gray tree frog (S)

MAMMALS (701-800)

- 701 Beaver
- 702 Whitetail deer
- 703 European fallow deer
- 704 Blackbeard Island deer
- 705 Opossum
- 706 Marsh rabbit
- 707 Rice rat
- 708 Raccoon
- 709 St. Simon Island raccoon
- 710 Mink
- 711 River otter (F)
- 712 Feral hog
- 713 Feral cow
- 714 Cumberland Island pocket gopher
- 715 Anastasia Island cotton mouse
- 716 Aquatic furbearers
- 717 Black bear (S)
- 718 Bobcat
- 719 Eastern gray squirrel
- 720 Eastern fox squirrel
- 721 Eastern cottontail
- 722 Delmarva fox squirrel (F)
- 723 Muskrat
- 724 Red fox
- 725 Bats
- 726 Gray fox
- 727 Striped skunk
- 728 Nutria
- 729 Longtail weasel
- 730 Colonial pocket gopher (S)
- 731 Wild ponies
- 732 Sika deer
- 733 Beach meadow vole
- 734 Block Island meadow vole
- 735 Pallid beach mouse (S)
- 736 Sherman's fox squirrel (S)
- 737 Florida mouse (S)
- 738 Florida panther (F)
- 739 Goff's pocket gopher (S)
- 740 Key Largo wood rat (S)
- 741 Lower keys cotton rat (S)
- 742 Key Largo cotton mouse (S)

HABITAT USE

Shown in RED for species with special status, BLUE for aquatic organisms and BROWN for terrestrial organisms

- | | |
|------------------------------|------------------------------|
| a Spawning ground | i Sport fishing/hunting area |
| b Nursery | g Migratory area |
| c Commercial harvesting area | h Nesting area |
| d Adult concentration | i Unusual distribution |
| e Overwintering area | or specimen |

Shown in BLUE; species with special status shown in RED-(F) or (S) indicates species protected by Federal or State Legislation (see text)

SYMBOL SPECIES



PLANTS (1-50)

- 1 Irish moss
- 2 Rockweed



INVERTEBRATES (51-100)

- 51 Crabs
- 52 Mussels
- 53 Oysters
- 54 Scallops
- 55 Clams
- 56 Worms
- 57 Shrimp
- 58 American lobster
- 59 Blue crab
- 60 Eastern oyster
- 61 European oyster
- 62 Bay scallop
- 63 Deep-sea scallop
- 64 Calico scallop
- 65 Surf clam
- 66 Hard clam
- 67 Soft shell clam
- 68 Brackish-water clam
- 69 Bloodworm
- 70 Sandworm
- 71 White shrimp
- 72 Brown shrimp
- 73 Northern shrimp
- 74 Rock crab
- 75 Jonah crab
- 76 Whelk
- 77 Ocean quahog
- 78 Pink shrimp
- 79 Stone crab
- 80 Spiny lobster



FISH (101-200)

- 101 Sharks, skates, rays
- 102 Herring
- 103 Salmon and trout
- 104 Catfish
- 105 Cod
- 106 Sunfish and bass
- 107 Drum
- 108 Flatfish
- 109 Longnose gar
- 110 Shortnose sturgeon (F)
- 111 Atlantic sturgeon (S)
- 112 American eel
- 113 Blueback herring
- 114 Hickory shad
- 115 Alewife
- 116 American shad (S)
- 117 Atlantic menhaden
- 118 Atlantic herring
- 119 Gizzard shad
- 120 Tarpon
- 121 Atlantic salmon
- 122 White catfish
- 123 Channel catfish
- 124 Yellow bullhead
- 125 Brown bullhead
- 126 Flat bullhead
- 127 Sea catfish
- 128 White perch
- 129 Striped bass
- 130 Black sea bass
- 131 Redbreast sunfish
- 132 Warmouth
- 133 Bluegill
- 134 Largemouth bass
- 135 Black crappie
- 136 Sheepshead
- 137 Spotted seatrout
- 138 Weakfish
- 139 Spot
- 140 Atlantic croaker
- 141 Southern kingfish
- 142 Northern kingfish
- 143 Gulf kingfish
- 144 Red drum
- 145 Star drum

000-00


- 146 Black drum
- 147 Summer flounder
- 148 Southern flounder
- 149 Winter flounder
- 150 Rainbow smelt
- 151 Atlantic tomcod
- 152 Threadfin shad
- 153 Carp
- 154 Atlantic mackerel
- 155 Chain pickerel
- 156 White bass
- 157 Northern puffer
- 158 Silver perch
- 159 Florida pompano
- 160 Bluefish
- 161 Spanish mackerel
- 162 Cobia
- 163 Mullet
- 164 White crappie
- 165 Redear sunfish
- 166 Smallmouth bass
- 167 Yellow perch
- 168 Pumpkinseed
- 169 Atlantic halibut
- 170 Atlantic cod
- 171 Pollock
- 172 Haddock
- 173 Hake
- 174 Bluefin tuna
- 175 Walleye
- 176 Northern pike
- 177 Scup
- 178 Tautog
- 179 Atlantic spadefish
- 180 Bay anchovy
- 181 Butterfish
- 182 Little tunny
- 183 Atlantic bonito
- 184 Brown trout
- 185 Cunner
- 186 Yellowtail flounder
- 187 Gulf flounder
- 188 Pinfish
- 189 King mackerel
- 190 Pigfish
- 191 White grunt
- 192 Tripletail
- 193 Ladyfish
- 194 Snook
- 195 Jack
- 196 Snapper
- 197 Grouper
- 198 Sailfish
- 199 Great barracuda
- 200 Maryland darter (F)



REPTILES AND AMPHIBIANS (201-250)

- 201 Green sea turtle (F)
- 202 Loggerhead sea turtle (F)
- 203 Hawksbill turtle (F)
- 204 Atlantic ridley turtle (F)
- 205 Leatherback turtle (F)


MAMMALS (251-300)

- 251 Florida manatee (F)
- 252 Atlantic bottlenose dolphin
- 253 Pigmy sperm whale
- 254 Short-finned pilot whale
- 255 Harbor seal
- 256 Gray seal
- 257 Right whale (F)
- 258 Atlantic spotted dolphin





FOR SALE BY U. S. GEOLOGICAL SURVEY, RESTON, VIRGINIA 22092, OR DENVER, COLORADO 80225



REFERENCE NO. 19



New York State Department of Environmental Conservation

MEMORANDUM

RECEIVED

TO: Al Machlin
FROM: Rocky J. Piaggione *RJP*
SUBJECT: Autotronics, Inc.

MAY 23 1983

DATE: 5/20/83

ENVIRONMENTAL QUALITY
REGION 1

Please be advised that the enclosed Order-on-Conser was sent to the above-named company on May 20, 1983. The case involves a relatively minor illegal disposal of 1, trichlorethane. If you have any questions, you can re me at (914)761-6660.

RJP/jg

STATE OF NEW YORK : DEPARTMENT OF ENVIRONMENTAL CONSERVATION
-----X

In the Matter of the Development and
Implementation of Remedial Measures under
Article 71 Title 27 of the Environmental
Conservation Law of the State of New York
(the "ECL") by

ORDER
ON
CONSENT

PETRON PRODUCTS, INC.

d/b/a AUTOTRONIC PRODUCTS, INC.

Respondent

WHEREAS:

1. Respondent owns and operates an industrial facility
located at 3360 Lawson Boulevard, Oceanside, County of Nassau,
State of New York (the "Facility").

2. Respondent disposed of industrial wastes without permit
on the southwestern portion of the real property immediately
adjacent to the Facility ("the Site").

3. Respondent and the Department of Environmental Conservation
have agreed that the purposes and goals of this Order shall be:

a) The development and implementation of a field
investigation to determine whether wastes disposed of at the Site
presently constitute a significant threat to the environment.

b) The determination of whether remedial action is
necessary at the Site; and

c) If remedial action is necessary at the Site, the development, implementation, administration and maintenance of a Disposal Site remedial program as defined by ECL Section 27-1301(3), in order to abate any present significant threat to the environment occurring as a result of wastes disposed of at the Site.

4. Respondent hereby consents to the issuing and entering of this Order, waives its right to a hearing herein, and agrees to be bound by the terms, provisions and conditions hereof. Respondent reserves its right to contest, by an action at law or equity, in a court of competent jurisdiction, any final determination of the Department made pursuant to, and subsequent to the effective date of this Order. In the event Respondent elects to contest any final determination of the Department, Respondent may commence such action at law or equity without exhausting any right to administrative review of such determination. The Department agrees that in the event the Respondent shall elect to contest any final determination of the Department, by an action in a court of competent jurisdiction, that the Department will not raise, as a defense to such action, that Respondent has not exhausted all of the administrative remedies available to it.

NOW, having considered this matter and being duly advised, it is ORDERED THAT:

5. Respondent pay a civil penalty in the amount of one thousand dollars (\$1,000.00) to the Department by certified check or money order made out to the Commissioner of the Department of Environmental Conservation, and sent to the Department.

6. Respondent shall have all industrial-commercial wastes generated by the Facility removed by a Department permitted industrial waste scavenger.

7. Within 45 (forty-five) days after the effective date of this Order, Respondent shall perform a field investigation at the Site, and shall submit to the Department a field investigation report (the "Report") which shall contain all data generated and all other information obtained during the field investigation, and shall include, but not be limited to, the following specific information:

(a) A plot plan of the Site showing property lines, lot lines and building locations.

(b) A minimum of two soil borings at a minimum of twelve inches in depth shall be taken from the southwestern portion of the site, near the fence, under Department supervision. Said soil samples shall be sent to a laboratory for analysis subject to Department approval.

(c) Said soil samples shall be transported to the laboratory under chain-of-custody and in accordance with all applicable regulations. Said soil samples shall be preserved at 4° C. at all times from collection until analyzed, and shall be

analyzed within 14 days from time of collection.

(d) Said soil samples shall be analyzed in accordance with EPA SW-611 Method 5030 Purge-and Trap and Method 8010 Halogenated Volatile Organics. The specific compounds to be identified include, but are not limited to: 1,1,1-trichloroethane

(e) All data collected and used in preparing the Report, including, but not limited to: soil boring logs and the analytical results of chemical tests performed on samples obtained from the Site.

8. Within thirty (30) days of the Department's receipt of the Report, the Department shall determine whether any remedial measures are appropriate and necessary, pursuant to the provision of Section 71-2727 (1) of the GL. Such remedial measures, if any, may include, but need not be limited to, additional field investigation. The Department hereby explicitly reserves the right to require additional field investigation to address specific off-site areas. Respondant shall undertake such remedial measures the specific requirements of which shall be incorporated in and made a part of this Order, and shall be attached hereto as an appendix.

9. All investigations, reports, plans and remedial measures required by this Order shall be prepared, designed and executed through the application of Requisite Technology. As used in this Order, Requisite Technology means accepted engineering, scientific

and construction principles and practices, subject to the Department's approval, which are technologically feasible and which will be most effective in carrying out the purposes and goals of this Order, and of any appendices hereto.

10. The Department shall have the right to obtain "split samples" of all substances and materials sampled by Defendant pursuant to this Order. As used herein, "split samples" shall mean whole samples divided into aliquots, to be tested by the Department for the purpose of comparative analysis.

11. Respondent shall provide notice to the Department of any excavating, drilling or sampling to be conducted pursuant to the terms of this Order at least five working days in advance of such activities.

12. Respondent shall permit any duly designated officer, employee, consultant, contractor or agent of the Department to enter upon the Site and to make or cause to be made such tests as are determined by the Department to be reasonably necessary and to ascertain Respondent's compliance or non-compliance with this Order.

13. Respondent shall not be in default of compliance with this Order if Respondent is unable to comply with any provision of this Order because of the action of national or local government body or court, an act of God, war, strike, riot, or catastrophe as to any of which negligence or willful misconduct on the part of Respondent is not shown.

shall apply in writing to the Department immediately upon obtaining knowledge of such an event and request an appropriate modification to this Order.

14. All reports and submissions herein required shall be made to the New York State Department of Environmental Conservation Division of Hazardous Waste Enforcement, 202 Westoneck Avenue, Room 304, White Plains, New York 10601-5381.

15. The effective date of this Order shall be the date this Order is signed by the Commissioner or his designee.

16. The provisions of this Order shall be deemed to bind Respondent, its agents, employees, successors and assigns, and all persons, firms and corporations acting under or for Respondent.

Dated: Albany, New York

HENRY G. WILLIAMS, Commissioner
New York State Department of
Environmental Conservation

CONSENT BY RESPONDENT

Respondent hereby consents to the issuing and entering of the foregoing Order, waives its right to a hearing herein as provided by law, and agrees to be bound by the provisions, terms and conditions contained herein.

PETRON PRODUCTS, INC.

d/b/a AUTRONIC, INC.

By: _____

Title: _____

Date: _____

STATE OF NEW YORK)

COUNTY OF)

s.s.:

On this _____ day of _____, 1983
before me personally came _____, to me known,
who, being by me duly sworn, did depose and say that he resides in _____
: that he is the _____
of _____
the corporation described in and which executed the foregoing
instrument; that he knew the seal of said corporation; that the
seal affixed to said instrument was such corporate seal; that it
was so affixed by the order of the Board of Directors of said
corporation, and that he signed his name thereto by like order.

NOTARY PUBLIC

REFERENCE NO. 20

CHEMICAL/SOLVENT WASTE REPORT

For each shipment of wastes, complete the following table with the indicated information. ATTACH COPIES OF MANIFESTS OR RECEIPTS FROM SCAVENGER FOR EACH SHIPMENT MADE.

[illegible]

List any accidental spills that occurred during the reporting period:

Date of Spill	Amount of Spill	Describe the nature of spill
		<p>RECEIVED</p> <p>FEB 20 1986</p> <p>NCDH</p> <p>BLRM</p>

Signature of Company <i>[Signature]</i>	Title <i>[Blank]</i>	Date: <i>1-1-1</i>
---	----------------------	--------------------

REFERENCE NO. 21

CHEMICAL/SOLVENT WASTE REPORT

For each shipment of wastes, complete the following table with the indicated information. ATTACH COPIES OF MANIFESTS OR RECEIPTS FROM SCAVENGER FOR EACH SHIPMENT MADE.

Date of Shipment	Type of Waste (Chemical, oil or solvents)	Amount Shipped	Shipped By			Shipped To (Final Disposal Site For Waste)
			Scavenger Name	Scavenger Address	Scavenger Number	
11/26/87	Trichloroethylene	55 gallons	Pride Solvents	75-88 LANARK ST W. Babylon, NY 11704	#0212	Pride Solvents

List any accidental spills that occurred during the reporting period:

Date of Spill	Amount of Spill	Describe the nature of spill

Signature of Company Representative *James H. Harker*

Title *Production Supervisor*

Date *7/12/88*

REFERENCE NO. 22

REFERENCE NO. 23



NASSAU COUNTY

DEPARTMENT of HEALTH

SOLID WASTE MANAGEMENT FACILITY PERMIT

Permit
Number **104**

Date
Issued February 6, 1984

Expiration
Date February 6, 1985

Type of Permit: ☐ Construction ☒ Operation ☒ Initial Issue ☐ Renewal ☐ Modification

Name of Facility: Autotronic Products, Inc.

Name of Permittee: Same

Address of Facility : 3300 Lawson Blvd, Oceanside, N.Y. 11572

Description of Facility : Mfg. Electronic Equipment

On-Site Supervisor: Mr. Clifford Bateman

GENERAL CONDITIONS

1. The permittee shall file in the office of the Nassau County Dept. of Health a notice of intention to commence work at least 48 hours in advance of the time of commencement and shall also notify said office promptly in writing of the completion of the work.
2. The permitted work shall be subject to inspection by an authorized representative of the Department who may order the work suspended if the public interest so requires.
3. As a condition of the issuance of this permit, the applicant has accepted expressly, by the execution of the application, the full legal responsibility for all damages, direct or indirect, of whatever nature, and by whomever suffered, arising out of the project described herein and has agreed to indemnify and save harmless the County from suits, actions, damages and costs of every name and description resulting from the said project.
4. All work carried out under this permit shall conform to the approved plans and specifications. Any amendments must be approved by the Nassau County Department of Health prior to their implementation.
5. The permittee is responsible for obtaining any other permits, approvals, easements and rights-of-way which may be required for this project.
6. By acceptance of this permit, the permittee agrees that the permit is contingent upon strict compliance with Article IX, Nassau County Public Health Ordinance and the special conditions cited below.

SPECIAL CONDITIONS

Authorizing Officer

John J. Dowling, M.D.

John J. Dowling, M.D., M.P.H. Commissioner of Health



DEPARTMENT of HEALTH

SOLID WASTE MANAGEMENT FACILITY PERMIT

Permit
Number

295

Date
Issued February 7, 1985

Expiration
Date February 6, 1986

Type of Permit:

☐ Construction

☒ Operation

☐ Initial Issue

☒ Renewal

☐ Modification

Name of Facility: Autotronic Products, Inc.

Name of Permittee: Same

Address of Facility: 3300 Lawson Blvd., Oceanside, New York 11572

Description of Facility: Mfg. electronic equipment

On-Site Supervisor: Mr. Clifford Bateman

GENERAL CONDITIONS

1. The permittee shall file in the office of the Nassau County Dept. of Health a notice of intention to commence work at least 48 hours in advance of the time of commencement and shall also notify said office promptly in writing of the completion of the work.
2. The permitted work shall be subject to inspection by an authorized representative of the Department who may order the work suspended if the public interest so requires.
3. As a condition of the issuance of this permit, the applicant has accepted expressly, by the execution of the application, the full legal responsibility for all damages, direct or indirect, of whatever nature, and by whomever suffered, arising out of the project described herein and has agreed to indemnify and save harmless the County from suits, actions, damages and costs of every name and description resulting from the said project.
4. All work carried out under this permit shall conform to the approved plans and specifications. Any amendments must be approved by the Nassau County Department of Health prior to their implementation.
5. The permittee is responsible for obtaining any other permits, approvals, easements and rights-of-way which may be required for this project.
6. By acceptance of this permit, the permittee agrees that the permit is contingent upon strict compliance with Article IX, Nassau County Public Health Ordinance and the special conditions cited below.

SPECIAL CONDITIONS

None

Authorizing Office

John J. Dowling, M.D.

John J. Dowling, M.D., M.P.H. Commissioner of Health

EH 758 11/83

THIS PERMIT MUST BE POSTED IN A CONSPICUOUS PLACE AT THE FACILITY

DH-4488. 11/83

REFERENCE NO. 24

LONG ISLAND WATER RESOURCES
BULLETIN NUMBER 1

RESULTS OF SUBSURFACE EXPLORATION
IN THE MID-ISLAND AREA OF WESTERN SUFFOLK COUNTY,
LONG ISLAND, NEW YORK

BY
JULIAN SOREN
U. S. GEOLOGICAL SURVEY

WITH A SECTION ON
POTENTIAL DEVELOPMENT OF GROUNDWATER
IN THE MID-ISLAND AREA

BY
PHILIP COHEN
U. S. GEOLOGICAL SURVEY

PREPARED BY
U. S. GEOLOGICAL SURVEY
IN COOPERATION WITH
SUFFOLK COUNTY LEGISLATURE
SUFFOLK COUNTY WATER AUTHORITY

PUBLISHED BY
SUFFOLK COUNTY WATER AUTHORITY

1971

UPPER CRETACEOUS SERIES

Raritan Formation

Lloyd Sand Member

The Lloyd Sand Member of the Raritan Formation comprises the Lloyd aquifer on Long Island. This unit consists mostly of beds and lenses of light- to medium-gray sand and gravelly sand, commonly containing small to large amounts of interstitial clay and silt, that are intercalated with beds and lenses of light- to dark-gray clay, silt, and clayey and silty sand.

Only two drill holes are known to have penetrated the Lloyd in the mid-island area. One hole partly penetrated the unit at the Pilgrim State Hospital, in Brentwood. The second hole, which is in the village of Lake Ronkonkoma, and which was one of the test holes drilled as part of this study, fully penetrated the unit. A log of the test hole describing lithology of the Lloyd is shown in table 1, S33379.

The surface of the Lloyd is roughly parallel to the bedrock surface. The Lloyd surface dips from an altitude of about 550 feet below sea level in the northwestern part of the area, to an altitude of about 1,250 feet below sea level in the southeastern part (pl. 2), and the unit's thickness ranges from about 260 feet to 360 feet from northwest to southeast, respectively. Plate 2 shows contours on the Lloyd surface. Plate 2 also shows contours on the bedrock surface; therefore, the Lloyd's thickness, in any part of the area, can be estimated by computing the local difference between the altitudes of the bedrock and Lloyd surfaces.

The Lloyd aquifer is moderately permeable. Its average horizontal permeability has been estimated by Lusczynski and Swarzenski (1966, p. 19), Sbister (1966, p. 20), and Soren (in press) to range between 400 and 500 gpd per sq ft (gallons per day per square foot) in Queens and Nassau Counties, west of the mid-island area. Warren and others (1968, p. 102) estimated the Lloyd's horizontal permeability to be 165 gpd per sq ft at the Brookhaven National Laboratory, about 12 miles east of the mid-island area. The section of Lloyd penetrated by the test well near Lake Ronkonkoma was fairly sandy and gravelly (table 1, S33379), and at this site the average horizontal permeability of the Lloyd probably is considerably more than 500 gpd per sq ft. Wells tapping the Lloyd in other parts of Long Island have been pumped at rates of as much as 1,600 gpm (gallons per minute), and the specific capacities of these wells (pumpage, in gallons per minute, divided by drawdown, in feet) have been reported to range from 3 to 40 gpm per foot of drawdown.

At present, there is no pumpage from the Lloyd aquifer in the mid-island area, mainly because of the great depth of the aquifer, and because more permeable aquifers are found at shallower depths. In addition to being at greater depth, the water from the Lloyd commonly has undesirably high concentrations of iron.

Clay Member

The clay member of the Raritan Formation (commonly referred to as the Raritan clay) completely covers the underlying Lloyd aquifer in the mid-island area, and confines water in that aquifer. The Raritan clay consists mostly of beds and lenses of light- to dark-gray clay, silt, and clayey and silty fine sand (table 1). Thin to thick sandy beds commonly occur in the unit from place to place, but these beds do not have great lateral extent. Laminae and thin beds of lignite and pyrite and disseminated particles of these substances are common in the clay beds of the unit. The thickness of the Raritan clay increases to the southeast, and ranges from about 150 feet in the northwestern part of the mid-island area to about 200 feet in the southeastern part.

The surface of the Raritan clay is roughly parallel to that of the underlying Lloyd Sand Member. The altitude of the surface of the Raritan clay ranges from about 300 feet below sea level in the northwestern part of the mid-island area, to about 1,050 feet below sea level in the southeastern part (pl. 3).

Matawan Group-Magothy Formation, Undifferentiated

The Matawan Group-Magothy Formation, undifferentiated, comprises the Magothy aquifer of Long Island. Deposits in this unit consist of beds and lenses of light-gray fine to coarse sand, containing traces to large amounts of interstitial clay and silt, intercalated with thin to thick beds and lenses of light- to dark-gray clay, silt, and clayey and silty sand (table 1). The clay and silt beds commonly contain laminae and thin beds of lignite. Disseminated lignite and pyrite also are common in the sand beds of the aquifer. Gravelly coarse sand is commonly found in the basal part of the aquifer. This coarse zone ranges in thickness from 100 to 150 feet west of the mid-island area to 150 to 200 feet in the mid-island area. The basal zone also commonly contains abundant interstitial clay and silt and many thin to thick beds and lenses of clay, silt, and clayey and silty sand.

The surface of the Magothy aquifer (pl. 4) is not planar as are the surfaces of the underlying units. The Magothy surface was deeply eroded during Tertiary time, and probably was considerably eroded in Pleistocene time. Consequently, the depth to the Magothy aquifer and the aquifer's thickness cannot be predicted as accurately as the depths and thicknesses of the underlying units. Many control points in addition to those already known are needed to accurately map the upper surface of the Magothy aquifer.

The highly irregular character of the surface of the Magothy aquifer is shown in plate 4. The upper surface of the aquifer ranges in altitude from as high as about 200 feet above sea level to as low as about 500 feet below sea level. The Magothy was completely removed by erosion in a buried valley near the South Huntington area, and in that area upper Pleistocene deposits lie directly on the Raritan clay. This buried valley was called the "Huntington buried valley" by Lubke (1964, pl. 3), and as mapped by Lubke, the valley extended about 2-1/2 miles south of the Northern State Parkway.

Information from wells drilled after Lubke's investigation indicates that the Huntington buried valley continues southeastward, joining another buried valley in the Deer Park area. From Deer Park, the valley appears to extend southeastward across Long Island to the Fire Island Pines area of Fire Island, about 10 miles southeast of Deer Park, where the Magothy surface was shown to be about 350 feet below sea level by Perlmutter and Todd (1965, pl. 8).

The Huntington and Deer Park buried valleys are separated by a divide across the buried valley system in the Deer Park area. The Huntington buried valley slopes steeply northwestward from the divide; the Deer Park buried valley has a gentle southward slope toward the Fire Island Pines area. The divide across the valley approximately coincides with the southern margin of the Ronkonkoma terminal moraine. (See the following section, "Pleistocene Series.") The steeper Huntington buried valley was probably overdeepened by scouring action of Pleistocene glaciation. Other buried valleys in the northern part of the mid-island area (pl. 4) are not as deep nor as extensive as the Huntington and Deer Park buried valleys.

A large depression in the Magothy surface is apparent in the St. James-Ronkonkoma area. Lubke (1964, pl. 3) showed the Magothy surface to be more than 200 feet below sea level in this area. More recent information indicates that the Magothy surface in this area is more than 500 feet below sea level (pl. 4). This large depression is here called the Ronkonkoma basin (pls. 4-5). The precise origin of this basin is not known, but it probably was at least partly a result of Pleistocene glacial scouring of a pre-existing valley system. The depression appears to have had no outlet, and its southernmost end coincides approximately with the southern margin of the Ronkonkoma terminal moraine.

Representative thicknesses of the Magothy aquifer are shown in geologic sections in plate 5. In these sections, the thickness of the Magothy ranges from about 300 to 800 feet. The estimated thickness of the Magothy aquifer in any part of the mid-island area can be computed by determining the difference between altitudes of the Magothy and Raritan surfaces as shown in plates 3 and 4. The Magothy aquifer is thickest (about 950 feet) in the southeastern corner of the project area, and it is thinnest in the bottom of the buried valleys. As previously noted, the aquifer is completely missing in part of the buried valley near South Huntington (pl. 4).

The permeability of the Magothy aquifer ranges widely. The estimated average horizontal permeability of the aquifer is about 500 gpd per sq ft in Nassau and Queens Counties (Luszczynski and Swarzenski, 1966, p. 19; Isbister, 1966, p. 23-24; and Soren, in press); however, the permeabilities of some beds in the aquifer may be as high as 2,000 gpd per sq ft (Isbister, 1966, p. 23). Public-supply wells screened in the Magothy aquifer of the mid-island area have yielded as much as 1,700 gpm, with specific capacities ranging from about 14 to 85 gpm per ft of drawdown.

PLEISTOCENE SERIES

Upper Pleistocene deposits

Pleistocene deposits of glacial origin mantle the surface of the mid-island area (pl. 1) and range in thickness from a few tens of feet in some localities to more than 600 feet in buried valleys. The approximate thickness of Pleistocene deposits at any place generally can be computed by determining the difference between the altitude of the land surface and the altitude of the surface of the Magothy aquifer.

Most and perhaps all the glacial materials on Long Island were deposited in Wisconsin time, and these materials generally are collectively termed upper Pleistocene deposits. The upper Pleistocene deposits in the mid-island area include terminal moraines, outwash deposits, ground moraine, and lake deposits. The Harbor Hill and Ronkonkoma terminal moraines form the irregular ridges trending east-northeast across the area. Outwash deposits derived from melted glacial ice lie south of the Ronkonkoma terminal moraine. Glacial lake deposits, which apparently were formed between the Ronkonkoma and Harbor Hill advances of the glaciers, lie within outwash deposits below the land surface, and occur mostly between the terminal moraines in the eastern half of the area, most notably in the Smithtown-St. James-Ronkonkoma area.

Ronkonkoma Terminal Moraine

The Ronkonkoma terminal moraine marks the farthest advance of glaciation on Long Island. The moraine is composed largely of crudely stratified sand and gravel. It underlies the highest parts of the mid-island area, tapering from an irregular broad band in the western part, to an irregular narrow ridge in the eastern part. (See plate 1.) The unit lies mostly above the water table and is, therefore, practically of no significance as a source of ground water; however, it is a difficult unit to drill through because of the large amounts of gravel, cobbles, and scattered boulders that it contains.

Harbor Hill Terminal Moraine

Only a very small part of this moraine is found in the mid-island area, in the extreme northwest corner near South Huntington (pl. 1). Most of this moraine is north of the mid-island area. The moraine's lithology and water-bearing characteristics are similar to those of the Ronkonkoma terminal moraine.

Outwash Deposits

The outwash deposits, which are found south of the Ronkonkoma terminal moraine and between the Harbor Hill and Ronkonkoma terminal moraines (fig. 2), are beds of sand and gravel that were deposited by glacial melt water. The

source of the rock materials in the outwash deposits is manifold. As the glaciers moved southward to Long Island, they plucked the bedrock and soils of the surfaces they slid over. Rock materials were incorporated into the ice in contact zones and were also pushed along the glacial front. As the ice melted in late Pleistocene time, the various rock materials were carried away by broad coalescing streams and sheets of water. Consequently, the outwash deposits are stratified, and because of the varied materials carried by the glacier, these deposits consist of a heterogeneous suite of rock types. The great diversity of rock and mineral suites in the Pleistocene deposits, along with the chemically unstable (easily decomposed) rocks and minerals, commonly facilitates differentiation of glacial from the Cretaceous deposits on Long Island.

Outwash deposits underlie the plain in the mid-island area south of the Ronkonkoma terminal moraine, where the major source of glacial deposition was material from the Ronkonkoma ice advance. A readvance of the glacial front followed recession of the Ronkonkoma ice front and resulted in the formation of the Harbor Hill terminal moraine. Lakes were formed in depressions and valleys between the Ronkonkoma and Harbor Hill terminal moraines, and clayey materials were deposited in these lakes. The inter-moraine areas also contain recessional deposits of outwash and ground moraine (see the following section, "Ground-Moraine Deposits") from the Ronkonkoma and Harbor Hill deglaciations, and these materials buried the clayey lake deposits.

The outwash deposits are thickest in the buried valleys and thinnest where the Cretaceous surface is closest to land surface (pl. 5). These deposits generally extend below the water table, and are a major source of ground water. Outwash deposits comprise most of the so-called upper glacial aquifer of Long Island, and because these deposits of sand and gravel contain virtually no interstitial clay and silt, the upper glacial aquifer is the most permeable aquifer on Long Island. The estimated average horizontal permeability of the outwash deposits is about 1,000 to 1,500 gpd per sq ft (Luszczynski and Swarzenski, 1966, p. 17; and Soren, in press). Warren and others (1968, p. 75) computed the horizontal permeability of outwash to be about 1,300 gpd per sq ft at the Brookhaven National Laboratory, east of the mid-island area. A horizontal permeability for outwash as high as about 2,500 gpd per sq ft has been reported in Nassau County, west of the project area (Isbister, 1966, p. 29).

Public-supply and other high-capacity wells screened in glacial outwash on Long Island have yielded as much as 1,700 gpm, and reported specific capacities of such wells range from less than 10 gpm per foot of drawdown to as much as about 200 gpm per foot of drawdown; however, the specific capacities range mostly from 50 to 100 gpm per foot of drawdown. (See section "Yields of Individual Wells.")

Ground-Moraine Deposits

Ground-moraine deposits commonly consist of unstratified and unsorted clay, silt, sand, gravel, cobbles, and boulders, deposited on the land surface as the glacial fronts receded. Ground-moraine deposits from the Ronkonkoma advance probably occur beneath the outwash in the area between the Ronkonkoma and Harbor Hill terminal moraines. Some ground-moraine deposits probably were partly reworked by glacial melt water from the Harbor Hill advance and probably appear similar to outwash in drilling samples.

Lake Deposits

A large lake apparently existed between the Ronkonkoma and Harbor Hill terminal moraines in the previously described Ronkonkoma basin. Deposits of light- to dark-brown and gray clay and silt of lacustrine origin, with some included beds of sand and gravel, occur between deposits of outwash in this area. The deposits are informally known as the Smithtown clay unit or Smithtown clay, and they were mapped and described by Lubke (1964, p. 22 and 26) as the "clay unit of Smithtown." Thin to significant thicknesses of this unit were penetrated at four of the test-drilling sites in the eastern half of the mid-island area. (See plate 5 and table 1, S22577, S22910T, S24769, and S24772). Apparently, it is thickest near the community of Lake Grove (not shown in plate 1) about 2.5 miles north of Lake Ronkonkoma, where about 300 feet of Pleistocene clay beds were penetrated in a drilled test hole (Jensen, H. M., oral commun., 1969).

Smaller glacial lakes probably also existed in other parts of the inter-morainal area. Many drilling logs from localities in the area indicate thin intercalated clay and fine sand beds between sand and gravel deposits. The extent of these lakes is not fully known, and they were probably small compared to the lake in which the Smithtown clay was deposited.

Veatch and others (1906, p. 61) suggested that present Lake Ronkonkoma, in the eastern part of the mid-island area, is in a depression made by a large ice block that was detached from the main glacial-front mass and buried by outwash deposits. Subsequent melting of the ice block presumably caused the depression in the land surface which then filled with water. Inasmuch as this study has shown that present Lake Ronkonkoma is in the Ronkonkoma basin, it seems possible that the location of the lake may merely reflect the fact that the ancient Ronkonkoma basin was not completely filled by glacial deposits.

The lake deposits do not yield significant quantities of water to wells because they are fine-textured and, accordingly, poorly permeable. However, the lake beds are hydrologically significant because they confine water in the underlying outwash deposits.

Miscellaneous Deposits

The Mannetto Gravel, of Pliocene age, and the Gardiners Clay, a Pleistocene interglacial marine deposit of pre-Wisconsin age, are two additional units of hydrologic significance in some parts of Long Island. However, their location and extent in the project area are poorly known, and they seem to occur in only a small part of the area.

The Mannetto Gravel was described and mapped by Fuller (1914, p. 80-85) from the western edge of the mid-island area to about as far east as the area between Wyandanch and Deer Park. The unit reportedly crops out at the tops of high hills, or near the crests of high hills capped by Ronkonkoma terminal moraine deposits. The author could not verify the location and extent of the Mannetto; consequently, the unit is not shown on the surficial geology map (pl. 1).

The Gardiners Clay is an interglacial marine deposit of Sangamon age. It is generally found in the south shore areas of Long Island where the depth to its surface is commonly 40 or more feet below sea level. The Gardiners Clay overlies Matawan-Magothy strata south of the mid-island area (Perlmutter and Todd, 1965, pl. 8), and some clay beds reported by well drillers in the southern part of the buried valley near Deer Park may be Gardiners Clay. However, this is uncertain, and the unit may not be present in the project area.

GROUND-WATER SYSTEM

SOURCE AND MOVEMENT OF GROUND WATER

The ground water on Long Island has its origin in precipitation that falls on the island. According to Cohen and others (1968, p. 36, 40, and 44), the precipitation on Long Island is disposed of as follows: nearly half returns to the atmosphere by evapotranspiration; a very small amount enters streams by direct runoff; and the remaining half percolates downward through the unconsolidated deposits to the water table and enters the ground-water reservoir.

The general ground-water movement on Long Island is from recharge areas near the center of the island to discharge areas at and near the shorelines. Ground water discharges by seepage into streams and by direct subsurface outflow into salty ground water, which in turn is hydraulically connected with bodies of salty surface water.

The horizontal components of the directions of ground-water flow in the upper glacial aquifer are shown in plate 6. In the vicinity of the major ground-water divide in the mid-island area (pl. 6), ground water generally moves downward from the upper glacial aquifer into the Magothy aquifer, and thence through the Raritan clay into the Lloyd aquifer. The vertical components of downward flow decrease with increasing distance both northward and southward of the divide. Beyond the northern and southern margins of the mid-island area, ground-water flow becomes virtually horizontal. Near

the shorelines, the direction of flow is reversed, and ground-water movement is upward from the deeper aquifers toward the surface. Thus, because of the character of the flow system, under natural conditions virtually all the recharge to the Magothy and Lloyd aquifers in western Suffolk County originated in the mid-island area, and all of that recharge ultimately discharged from the ground-water system near the shorelines.

The movement of ground water through Long Island's aquifers in the horizontal direction is generally more rapid than movement in the vertical direction because of the occurrence of interbedded fine- and coarse-grained layers, and because the largest dimensions of unevenly shaped particles in the individual layers tend to be oriented horizontally. Approximate rates of ground-water movement can be computed from hydraulic gradients and estimated coefficients of permeability and porosities of the aquifers. In 1968, water in the upper glacial aquifers in the project area was moving horizontally at rates from less than 0.5 foot per day at points distant from centers of pumping, to hundreds of feet per day near the screens of pumping wells. At the same time, water in the Magothy aquifer was moving horizontally at rates from less than 0.2 foot per day at points distant from pumping, to hundreds of feet per day near the screens of pumping wells.

HYDRAULIC INTERCONNECTION OF AQUIFERS

The aquifers of Long Island are hydraulically interconnected. Layers of clay and silt within an aquifer or between aquifers serve to confine water below them, but they do not completely prevent the vertical movement of water through them. Ground water moves downward readily through coarse outwash deposits in the upper glacial aquifer. Vertical movement of water through the Magothy aquifer is impeded by beds and lenses of clay and silt. Because the clay and silt strata in the Magothy are not continuous, some water may move around lenses of this material in addition to moving slowly through the fine-grained strata.

The contact between the upper glacial and Magothy aquifers is not regular either in attitude or in composition of the contact surfaces. Glacial deposits in buried valleys are in lateral contact with truncated sandy beds in the Magothy. In the buried valleys water can laterally enter the Magothy at great depth directly from the glacial deposits, rather than the water having to move vertically to the same depth through less permeable Magothy beds. In the Huntington buried valley, glacial deposits extend completely through the Magothy aquifer to the underlying Raritan clay. (See plate 4.) In addition to the good hydraulic continuity between the upper glacial and Magothy aquifers in the buried valleys, good hydraulic continuity occurs between the aquifers outside the buried valleys where glacial sand and gravel deposits lie directly on Magothy sand beds. Thus, a fairly good hydraulic connection exists between the upper glacial and Magothy aquifers over large parts of the mid-island area, and the configuration of the piezometric surface of the Magothy aquifer is generally similar to that of the water table. However, in the mid-island area hydraulic heads in the Magothy are lower than those in the upper glacial aquifer because of the downward component of ground-water movement in the area.

The thick areally persistent Raritan clay that lies between the Magothy and Lloyd aquifers impedes but does not prevent downward movement of ground water into the Lloyd aquifer, and water in the Lloyd is tightly confined between the Raritan clay and bedrock. Downward leakage into the bedrock is negligible.

Figures 2 and 3 show hydrographs of wells screened in the upper glacial aquifer and the Magothy aquifer at the test-drilling sites in Brentwood and Hauppauge. At both sites, the heads in the deepest wells in the Magothy aquifer are about 2.5 to 3 feet lower than the heads in the shallowest wells in the upper glacial aquifer. The loss of head downward reflects the downward movement of ground water in the mid-island area. The hydrographs in figures 2 and 3 show that the heads in these two aquifers in the project area decrease at a fairly uniform rate with increasing depth. In addition, water-level fluctuations in the two groups of wells were very similar. Both of these facts, the uniform decrease in head and the similar water-level fluctuations, reflect the high degree of hydraulic interconnection between the upper glacial and Magothy aquifers.


The average vertical permeability of the Magothy aquifer is only poorly known. Estimates range from less than 1 to about 30 gpd per sq ft. Assuming that it averages about 5 gpd per sq ft in the mid-island area, the computed amount of downward ground-water movement through the Magothy aquifer in the vicinity of the ground-water divide in 1968 was about 0.4 mgd (million gallons per day) per square mile, and the estimated velocity of the downward movement was about 0.006 foot per day.

Because of the low permeability of the Raritan clay, the hydraulic-head loss across this unit is very much larger than the head loss across a comparable thickness of the Magothy and upper glacial aquifers. At the easternmost test site in the village of Lake Ronkonkoma, wells were screened near the base of the Magothy and near the top of the Lloyd aquifers (pl. 5, section A-A', S33379-80). In 1968, the head near the base of the Magothy aquifer (about 45.5 feet above sea level) was about 11.5 feet higher than the head in the Lloyd aquifer (about 34 feet above sea level). Head losses across the Raritan clay at localities east and west of the Lake Ronkonkoma area differ considerably. At Upton, about 12 miles east of the mid-island area, the head loss across the clay was about 6 feet in 1968; and at Plainview (in Nassau County), about 3 miles southwest of Melville, the head loss across the clay was about 42 feet. The differences in head loss from place to place are largely a result of differences in the vertical permeability and thickness of the Raritan clay.

The head in the Lloyd aquifer at Lake Ronkonkoma in 1968 (about 34 feet above sea level) was higher than either of the heads in the Lloyd at Upton (about 30.5 feet above sea level) and at the Suffolk-Nassau boundary (about 27.5 feet above sea level). The head in the Lloyd at Terryville, about 7 miles northeast of the Ronkonkoma area was about 21 feet above sea level in 1968, and it was 19 feet above sea level at Fire Island State Park in 1968, about 13 miles to the southwest. These data suggest that water in the Lloyd aquifer is moving radially from the Lake Ronkonkoma area. The estimated rate of horizontal movement of water in the Lloyd aquifer in the project area in 1968, was on the order of 0.1 foot per day.

IN COOPERATION WITH THE
SUFFOLK COUNTY WATER AUTHORITY
AND
SUFFOLK COUNTY LEGISLATURE

LONG ISLAND WATER RESOURCES BULLETIN NUMBER 1 PLATE 1
PUBLISHED BY SUFFOLK COUNTY WATER AUTHORITY



Prepared by
UNITED STATES DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY, Albany, N. Y.

IN COOPERATION WITH THE
SUFFOLK COUNTY WATER AUTHORITY
AND
SUFFOLK COUNTY LEGISLATURE

LONG ISLAND WATER RESOURCES BULLETIN NUMBER 1 PLATE 4
PUBLISHED BY SUFFOLK COUNTY WATER AUTHORITY



EXPLANATION

Approximate contour on
Matawan Group-Magothy Formation,
undifferentiated, and on
Magothy Formation, undifferentiated.
Notes: altitudes of contour lines based
on Matawan Group-Magothy Formation,
undifferentiated. Dashed where notes
Contour interval, 50 and 100 feet. The
contour is a line.

Well that penetrates
Matawan Group-Magothy Formation,
undifferentiated surface.

Deep well that does not penetrate
Matawan Group-Magothy Formation,
undifferentiated surface.

Approximate topography contour.


MAP OF MID-ISLAND AREA SHOWING CONTOURS ON THE SURFACE OF THE MATAWAN GROUP-MAGOTHY FORMATION, UNDIFFERENTIATED

Prepared by
UNITED STATES DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY, Albany, N.Y.

IN COOPERATION WITH THE
SUFFOLK COUNTY WATER AUTHORITY
AND
SUFFOLK COUNTY LEGISLATURE

LONG ISLAND WATER RESOURCES BULLETIN NUMBER 1 PLATE 3
PUBLISHED BY SUFFOLK COUNTY WATER AUTHORITY

NOTE: In this area, contour is not
on top of the unit, contour
is on surface.



1000

500

Structure contour

Member of Raritan Formation
Distance in feet
(Control based on particular
contour interval)

Distance in feet
(Control based on particular
contour interval)

Distance in feet
(Control based on particular
contour interval)

MAP OF MID ISLAND AREA SHOWING CONTOURS ON THE SURFACE OF THE CLAY MEMBER OF THE RARITAN FORMATION